

## Mack Energy Closed Loop System Design Plan

30-025 - 39522

Equipment list.

2- 414 Swaco Centrifuges

2- 4 screen Mongoose shale shakers

2- CRI Bins with track system

2- 500 BBL frac tanks for fresh water ..

2- 500 BBL frac tanks for brine water

---

### Operations and Maintenance

Closed Loop equipment will be inspected daily by each tour and any necessary maintenance performed.

Any leak in system will be repaired and /or contained immediately.

OCD notified within 48 hours.

Remediation process started.

### Closure Plan

During drilling operations all liquids, drilling fluids and cuttings will be hauled off by CRI(Controlled Recovery Inc. Permit NM-01-0006).

