

**DISTRICT I**  
P.O. Box 1980, Hobbs, NM 88240

**DISTRICT II**  
P.O. Drawer DD, Artesia, NM 88210

**DISTRICT III**  
1000 Rio Brazos Rd., Aztec, NM 87410

## OIL CONSERVATION DIVISION

2040 Pacheco St.  
Santa Fe, NM 87505

WELL API NO. 30-025-36144	
Indicate Type of Lease STATE <input type="checkbox"/> FEE <input checked="" type="checkbox"/>	
State Oil & Gas Lease No. N/A	
Lease Name or Unit Agreement Name Phillips	
Well No. 1	
Pool name or Wildcat Nadine : Drinkard-Abo	
Well Location Unit Letter <u>E</u> : <u>1980</u> Feet From The <u>North</u> Line and <u>330</u> Feet From The <u>West</u> Line Section <u>19</u> Township <u>19S</u> Range <u>39E</u> NMPM <u>Lea</u> County	
Elevation (Show whether DF, RKB, RT, GR, etc.) 3577 GR	

**SUNDRY NOTICES AND REPORTS ON WELLS**  
(DO NOT USE THIS FORM FOR PROPOSALS TO DRILL OR TO DEEPEN OR PLUG BACK TO A DIFFERENT RESERVOIR. USE "APPLICATION FOR PERMIT" (FORM C-101) FOR SUCH PROPOSALS.)

Type of Well:  
OIL WELL ☒ GAS WELL ☐ OTHER

Name of Operator  
Trilogy Operating, Inc

Address of Operator  
P.O. Box 7606, Midland Texas 79708

11 Check Appropriate Box to Indicate Nature of Notice, Report, or Other Data

### NOTICE OF INTENTION TO:

PERFORM REMEDIAL WORK ☐ PLUG AND ABANDON ☐  
TEMPORARILY ABANDON ☐ CHANGE PLANS ☐  
PULL OR ALTER CASING ☐  
OTHER: ☐


### SUBSEQUENT REPORT OF:

REMEDIAL WORK ☐ ALTERING CASING ☐  
COMMENCE DRILLING OPNS. ☐ PLUG AND ANBANDONMENT ☐  
CASING TEST AND CEMENT JOB ☐  
OTHER: REENTRY OF PLUGGED WELLBORE ☒

12 Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work) SEE RULE 1103.

4/08/03 - 4/10/03

MIRU reentry eqpt. - drill out cement plugs as follows: 1) 260'-417' , 2) 1548'-1758' , 3) 3650'-3801' , 4) 5338'-5348' , 5) 7233'-7418'  
wash to bottom - TD @ 7707' - POH w/ tbg & bit, LDDP - RIH w/ 188 jts 5 1/2" - 17# -N80 csg to a setting depth of 7700'  
Cement w/ lead - 900 sx poz c (65:35) + 6% gel + 5% salt + 4/10% FL-62 + 1/4#/sx celloflake  
tail - 700 sx class "H" + 5/10% FL-62 - circulated 10 sx cement to surface  
RDMO Reentry eqpt - wait on completion



I hereby certify that the information above is true and complete to the best of my knowledge and belief.

SIGNATURE [Signature] TITLE Engineer

DATE 04-14-03

TYPE OR PRINT NAME

TELEPHONE NO.

(This space for State Use)

APPROVED BY

[Signature]

OCT FIELD REPRESENTATIVE II/STAFF MANAGER APR 18 2003  
DATE

CONDITIONS OF APPROVAL, IF ANY: