Submit 3 Copies To Appropriate I Office	District State of New Energy, Minerals and Na	Mexico		Form C-103
District I 1625 N French Dr., Hobbs, NM	Dicigy, Winderals and W.	aturai Resources	WELL API NO.	May 27, 2004
1213(1)(1)11	OH CONGEDIATE	ONDIVICION	30-025-36106	
1301 W. Grand Ave., Artesia, NM	88210 OIL CONSERVATI	UN DIVISIUN Erancia Dr	5. Indicate Type of Lease	
1000 Rio Brazos Rd , Aztec, NM 8	AUG 19 2010 1220 South St. Santa Fe, NA	1 27505	<u> </u>	
District IV. 1220 S. St. Francis Dr., Santa Fe,		107505		
1220 S. St. Francis Dr., Santa Fe,			6. State Oil & Gas Lease No	•
SUNDRY NOTICES AND REPORTS ON WELLS  (DO NOT USE THIS-FORM FOR PROPOSALS TO DRILL OR TO DEEPEN OR PLUG BACK TO A DIFFERENT RESERVOIR. USE "APPLICATION FOR PERMIT" (FORM C-101) FOR SUCH PROPOSALS.)			7. Lease Name or Unit Agree W.M. Rinewalt	ement Name:
1. Type of Well: Oil Well  Gas Well  Other			8. Well Number	,
2. Name of Operator			9. OGRID Number	
OXY USA Inc.			16696	
3. Address of Operator			10. Pool name or Wildcat	
	land, TX 79710-0250		Eunice San Andrers, SW	
4. Well Location				
Unit LetterE	: 1930 feet from the	north line and	feet from the	
Section .	4 Township 22S	Range 37E	NMPM County	Lea
	11. Elevation (Show wheth		c.)	
Pit or Below-grade Tank Applicat	tion O or Closure O	3440'		
				(
	ndwater Distance from nearest f			
Pit Liner Thickness:	mil Below-Grade Tank: Volui	nebbls; Construction	on Material	
	F INTENTION TO:  K PLUG AND ABANDON  CHANGE PLANS  MULTIPLE	REMEDIAL WORK	NG OPNS. PLUG A	NG CASING
	COMPLETION	CEMENT JOB		
OTHER:		OTHER:		
of starting any proposed or recompletion.	8-5/8" 32# csg @ 1110' w/ 5-1/2" 15.5# csg @ 4000' v 1. RIH & Set CIBP @ 3820' w/ 2. M&P 30sx cmt @ 2600-2400' 3. M&P 25sx cmt @ 1200-1060' 4. M&P 25sx cmt @ 150' to Sur 10# MLF between plugs	ple Completions: Attach -3872-3890' 650sx, 12-1/4" hole, w/660sx, 7-7/8" hole 25sx cmt to 3640' - WOC-TAG rface The 24 h	wellbore diagram of proposed  TOC-Surface-Circ  TOC-Surf-Circ  Oil Conservation Division Musions prior to the beginning of	completion  st be notified plugging operations.
I hereby certify that the inform	ation above is true and complete to the	ne best of my knowledge	and belief. I further certify that a	ny pit or below-
SIGNATURE	cted or closed according to NMOCD guideli	nes, a general permit [	or an (attached) alternative OCD	-approved plan 🔲 ප(ලේ(ට
Type or print name David St	· F		david_stewart@oxy.com	
			Telephone No. 4	32-685-5/1/
For State Use Only	-/1) //·M.	DISTRIAT + a	SHIDEDUAN- ALL	6 2 <sup>0</sup> 2010
APPROVED BY CAM	FW, YW T	TILE DISTRICT 1.5	SUPERVISOF, DATE AU	D & 2 7010
Conditions of Approval, if any:				

. \*

OXY USA Inc. - Proposed W.M. Rinewalt #4 API No. 30-025-36106


25sx @ 150'-Surface

12-1/4" hole @ 1110' 8-5/8" csg @ 1110' w/ 650sx-TOC-Surf-Circ

25sx @ 1200-1060' WOC-Tag

30sx @ 2600-2400'


CIBP @ 3820' w/ 25sx



7-7/8" hole @ 4000' 5-1/2" csg @ 4000' w/ 660sx-TOC-Surf-Circ

Perfs @ 3872-3890'

OXY USA Inc. - Current W.M. Rinewalt #4 API No. 30-025-36106



TD-4000'

12-1/4" hole @ 1110' 8-5/8" csg @ 1110' w/ 650sx-TOC-Surf-Circ

7-7/8" hole @ 4000' 5-1/2" csg @ 4000' w/ 660sx-TOC-Surf-Circ

Perfs @ 3872-3890'