

State of New Mexico  
Energy, Minerals and Natural Resources

OIL CONSERVATION DIVISION  
1220 South St. Francis Dr.  
Santa Fe, New Mexico 87504-2088

SUNDRY NOTICES AND REPORTS ON WELLS (DO NOT USE THIS FORM FOR PROPOSALS TO DRILL OR TO DEEPEN OR PLUG BACK TO A DIFFERENT RESERVOIR. USE "APPLICATION FOR PERMIT" (FORM C-101) FOR SUCH PROPOSALS.)		WELL API NO. 30-025-35327
1. Type of Well: Oil Well <input type="checkbox"/> Gas Well <input checked="" type="checkbox"/> Other		5. Indicate Type of Lease STATE <input checked="" type="checkbox"/> FEE <input type="checkbox"/>
2. Name of Operator Yates Petroleum Corporation		6. State Oil & Gas Lease No. V-4826
3. Address of Operator 105 South 4th Str., Artesia, NM 88210		7. Lease Name or Unit Agreement Name North Papalotes State Unit
4. Well Location Unit Letter <u>A</u> : <u>990</u> feet from the <u>North</u> line and <u>660</u> feet from the <u>East</u> line Section <u>36</u> Township <u>14S</u> Range <u>34E</u> NMPM County <u>Lea</u>		8. Well No. 1
10. Elevation (Show whether DF, RKB, RT, GR, etc.) 4064' GR		9. Pool Name or Wildcat Morton Morrow (Gas)

## 11. Check Appropriate Box to Indicate Nature of Notice, Report, or Other Data

## NOTICE OF INTENTION TO:

PERFORM REMEDIAL WORK ☐ PLUG AND ABANDON ☐  
 TEMPORARILY ABANDON ☐ CHANGE PLANS ☐  
 PULL OR ALTER CASING ☐ MULTIPLE COMPLETION ☐  
 OTHER: ☐


## SUBSEQUENT REPORT OF:

REMEDIAL WORK ☐ ALTERING CASING ☐  
 COMMENCE DRILLING OPNS. ☐ PLUG AND ABANDONMENT ☐  
 CASING TEST AND CEMENT JOB ☐  
 OTHER: Perforate/Stimulate ☒

12. Describe proposed or completed operations. (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work). SEE RULE 1103. For Multiple Completions: Attach wellbore diagram of proposed completion or recompletion.

**11-24-03 to 2-6-04** Perforated Austin Cycle 13555-68' w/26 .42" holes. Pumped 190 bbls 7% down annulus. Pumped 500 gal acid. Perforated Mississippian 13711-17' (6), 13720-28' (8), 13732-39' (7) and 13742-66' (2) for total of 44 - .42" holes. Acidized w/5000 gal 15% NEFE w/50 balls. Set 5-1/2" CIBP @ 13540' and capped w/35' cement. Set CIBP @ 13450' and capped w/35' cement. Perforated Morton Morrow 13299-308' w/60 .42" holes. Acidized w/1000 gal 7-1/2% Morrow acid. Frac'd w/34000 gal 40# Medallion, 30% CO2 foam w/16000# 20/40 Bauxite.

**2-7/8" tubing and packer @ 13200'.**



I hereby certify that the information above is true and complete to the best of my knowledge and belief.

SIGNATURE Stormi Davis TITLE Regulatory Compliance Technician DATE 2/11/04

Type or print name Stormi Davis

Telephone No. 505-748-1471

(This space for State use)

APPROVED BY Harry W. Wink DATE FEB 17 2004

Conditions of approval, if any: