

ATS-18-146

RECEIVED

Form 3160-3  
(April 2004)

OCD Hobbs

MAR 28 2011  
HOBBSOCD

FORM APPROVED  
OMB No. 1004-0137  
Expires March 31, 2007

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT

APPLICATION FOR PERMIT TO DRILL OR REENTER

1a. Type of work: <input checked="" type="checkbox"/> DRILL <input type="checkbox"/> REENTER		5. Lease Serial No. NMLC-0294051A
1b. Type of Well: <input checked="" type="checkbox"/> Oil Well <input type="checkbox"/> Gas Well <input type="checkbox"/> Other <input type="checkbox"/> Single Zone <input type="checkbox"/> Multiple Zone		6. If Indian, Allottee or Tribe Name N/A
2. Name of Operator COG Operating LLC		7. If Unit or CA Agreement, Name and No. N/A
3a. Address 550 W. Texas, Suite 1300 Midland TX 79701		8. Lease Name and Well No. <b>&lt;302456&gt;</b> B C Federal #60
3b. Phone No. (include area code) (432) 685-4385		9. API Well No. 30-025- <b>40097</b>
4. Location of Well (Report location clearly and in accordance with any State requirements.) At surface 1305' FNL & 915' FWL, Unit D At proposed prod. zone 1650' FNL & 990' FWL, Unit E		10. Field and Pool, or Exploratory Maljamar; Yeso, West <b>&lt;44500&gt;</b>
14. Distance in miles and direction from nearest town or post office* 2.5 miles SW of Maljamar, NM		11. Sec., T. R. M. or Blk. and Survey of Area Sec 20, T17S, R32E
15. Distance from proposed* location to nearest property or lease line, ft. (Also to nearest drig. unit line, if any) 915'	16. No. of acres in lease 640	17. Spacing Unit dedicated to this well 40
18. Distance from proposed location* to nearest well, drilling completed, applied for, on this lease, ft. 700'	19. Proposed Depth 7122' MD 7100' TVD	20. BLM/BIA Bond No. on file NMB000215
21. Elevations (Show whether DF, KDB, RT, GL, etc.) 3968' GL	22. Approximate date work will start* 01/31/2011	23. Estimated duration 10 days

24. Attachments

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No. 1, shall be attached to this form:

- |   |  |
|---|--|
| 1. Well plat certified by a registered surveyor.  | 4. Bond to cover the operations unless covered by an existing bond on file (see Item 20 above).    |
| 2. A Drilling Plan.   | 5. Operator certification  |
| 3. A Surface Use Plan (if the location is on National Forest System Lands, the SUPO shall be filed with the appropriate Forest Service Office). | 6. Such other site specific information and/or plans as may be required by the authorized officer. |

25. Signature	Name (Printed/Typed) Kelly J. Holly	Date 11/03/2010
Title Permitting Tech		

Approved by (Signature) /s/ JEANETTE MARTINEZ	Name (Printed/Typed)	Date MAR 24 2011
Title FIELD MANAGER	Office CARLSBAD FIELD OFFICE	

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.  
Conditions of approval, if any, are attached.

APPROVAL FOR TWO YEARS

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

\*(Instructions on page 2)

Roswell Controlled Water Basin

K2 03/28/11

Approval Subject to General Requirements  
& Special Stipulations Attached

MAR 29 2011

PETROLEUM ENGINEER

SEE ATTACHED FOR  
CONDITIONS OF APPROVAL

dm

DISTRICT I  
1625 N. FRENCH DR., HOBBS, NM 88240

DISTRICT II  
1301 W. GRAND AVENUE, ARTESIA, NM 88210

DISTRICT III  
1000 Rio Brazos Rd., Aztec, NM 87410

DISTRICT IV  
1220 S. ST. FRANCIS DR., SANTA FE, NM 87505

State of New Mexico  
Energy, Minerals and Natural Resources Department

OIL CONSERVATION DIVISION  
1220 SOUTH ST. FRANCIS DR.  
Santa Fe, New Mexico 87505

RECEIVED

MAR 28 2011

HOBBSUCD

Form C-102  
Revised October 12, 2005  
Submit to Appropriate District Office  
State Lease - 4 Copies  
Fee Lease - 3 Copies

WELL LOCATION AND ACREAGE DEDICATION PLAT

☐ AMENDED REPORT

API Number 30-025 - 40097	Pool Code 44500	Pool Name Maljamar; Yeso, West
Property Code 302456	Property Name BC FEDERAL	Well Number 60
OGRID No. 229137	Operator Name COG OPERATING, LLC	Elevation 3968'

Surface Location

UL or lot No.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County
D	20	17-S	32-E		1305	NORTH	915	WEST	LEA

Bottom Hole Location If Different From Surface

UL or lot No.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County
E	20	17-S	32-E		1650	NORTH	990	WEST	LEA

Dedicated Acres 40	Joint or Infill	Consolidation Code	Order No.
-----------------------	-----------------	--------------------	-----------

NO ALLOWABLE WILL BE ASSIGNED TO THIS COMPLETION UNTIL ALL INTERESTS HAVE BEEN CONSOLIDATED  
OR A NON-STANDARD UNIT HAS BEEN APPROVED BY THE DIVISION

<p>SEE DETAIL S.L. GRID AZ.-167°25'47" HORZ. DIST.-353.1' 915' 1305' 1650' 990' B.H. 3961.4' 3969.0' 600' 3963.1' 3970.6' 600'</p> <p>DETAIL 600' 3963.1' 3970.6'</p> <p>GEODETIC COORDINATES NAD 27 NME SURFACE LOCATION Y=663798.9 N X=665766.4 E LAT.=32.823707° N LONG.=103.793718° W BOTTOM HOLE LOCATION Y=663454.4 N X=665843.2 E</p> <p>PERMEATION POINT 1000' FALZ 983' FAL</p>	<p>OPERATOR CERTIFICATION</p> <p>I hereby certify that the information herein is true and complete to the best of my knowledge and belief, and that this organization either owns a working interest or unleased mineral interest in the land including the proposed bottom hole location or has a right to drill this well at this location pursuant to a contract with an owner of such mineral or working interest, or to a voluntary pooling agreement or a compulsory pooling order heretofore entered by the division.</p> <p>Signature: Kelly J. Holly Date: 11-03-2010 Printed Name: Kelly J. Holly</p> <p>SURVEYOR CERTIFICATION</p> <p>I hereby certify that the well location shown on this plat was plotted from field notes of actual surveys made by me or under my supervision, and that the same is true and correct to the best of my belief.</p> <p>OCTOBER 18 2010 Date Surveyed Signature: Gary A. Eidson Professional Surveyor 12641 10.11.0938 Certificate No. 12641 RONALD J. EIDSON 3239</p>
--	--

RECEIVED

MAR 28 2011  
HOBBSOCD

## MASTER DRILLING PROGRAM

### 1. Geologic Name of Surface Formation

Quaternary

### 2. Estimated Tops of Important Geologic Markers:

Quaternary	Surface
Rustler	680'
Top of Salt	900'
Base of Salt	1700'
Yates	2010'
Seven Rivers	2375'
Queen	2980'
Grayburg	3355'
San Andres	3700'
Glorietta	5260'
Paddock	5310'
Blinbry	5870'
Tubb	6810'

### 3. Estimated Depths of Anticipated Fresh Water, Oil and Gas

Water Sand	150'	Fresh Water
Grayburg	3355'	Oil/Gas
San Andres	3700'	Oil/Gas
Glorietta	5260'	Oil/Gas
Paddock	5310'	Oil/Gas
Blinebry	5870'	Oil/Gas
Tubb	6810'	Oil/Gas

No other formations are expected to give up oil, gas or fresh water in measurable quantities. Setting 13 3/8" casing to ~~650'~~ and circulating cement back to the surface will protect the surface fresh water sand. The Salt Section will be protected by setting 8 5/8" casing to ~~2100'~~ and circulating cement, in a single or multi-stage job and/or with an ECP, back to the surface. Any shallower zones above TD, which contain commercial quantities of oil and/or gas, will have cement circulated across them. This will be achieved by cementing, with a single or multi-stage job, the 5 1/2" production casing back 200' into the intermediate casing, to be run at TD. If wellbore conditions arise that require immediate action and/or a change to this program, COG Operating LLC personnel will always react

See  
COA

#### 4. Casing Program

See  
COR

Hole Size	Interval	OD Casing	Weight	Grade	Jt., Condition	burst/collapse/tension
17 1/2"	0-650'750'	13 3/8"	48#	H-40orJ-55	ST&C/New	6.03/2.578/10.32
11"	0-2100'2500'	8 5/8"	24or32#	J-55	ST&C/New	1.85/1.241/4.78
7 7/8"	0-T.D.	5 1/2"	15.5or17#	J-55orL-80	LT&C/New	1.59/1.463/2.05

#### 5. Cement Program See COR

13 3/8" Surface Casing:

LEAD Class C, 4% Gel, 2% CaCl<sub>2</sub>, .25 pps CF, 325 sx, yield-1.75 + TAIL 200 sx w/ 2% CaCl<sub>2</sub>, 0.25 pps CF, yield-1.32. 133% excess

8 5/8" Intermediate Casing:

##### 11" Hole:

**Single Stage:** LEAD 50:50:10 C:Poz:Gel w/ 5% Salt +0.25% CF, 375 sx, yield-2.45 + TAIL Class C w/2% CaCl<sub>2</sub>, 200 sx, yield-1.32, back to surface. 133% excess

**Multi-Stage:** Stage 1: Class C w/2% CaCl<sub>2</sub>, 400 sx, yield - 1.32; 48% excess  
Stage 2: Class C w/2% CaCl<sub>2</sub>, 200 sx, yield - 1.32, back to surface, 48% excess; assumption for tool is lost circulation. Multi stage tool to be set at approximately, depending on hole conditions, 700' (50' below the surface casing). Cement volumes will be adjusted proportionately for depth changes of multi stage tool.

5 1/2" Production Casing:

**Single Stage:** LEAD 35:65:6 C:Poz:Gel w/ 5% Salt + 5 pps LCM + 0.2% SMS + 0.3% FL-52A + 0.125 pps CF, 500 sx, yield-2.05 + TAIL 50:50:2 C:Poz:Gel w/ 5% Salt + 3 pps LCM + 0.6% SMS + 1% FL-25 + 1% BA-58 + 0.3% FL-52A + 0.125 pps CF, 400 sx, yield-1.37, to 200' minimum tie back to intermediate casing. 30% excess back to surface.

**Multi-Stage:** Stage 1: (Assumed TD of 7000') 50:50:2, C:Poz:Gel w/ 5% Salt + 3

pps LCM + 0.6% SMS + 1% FL-25 + 1%  
BA-58 + 0.3% FL-52A + 0.125 pps CF, 500  
sx, yield - 1.37, 13% excess; Stage 2:  
LEAD 50:50:2 C:Poz:Gel w/ 5% Salt + 3  
pps LCM + 0.6% SMS + 1% FL-25 + 1%  
BA-58 + 0.3% FL-52A + 0.125 pps CF, 450  
sx, yield - 1.37, + TAIL Class C w/ 0.3% R-  
3 + 1.5% CD-32, 250 sx, yield - 1.02 43%  
excess calculated back to surface. Multi  
stage tool to be set at approximately,  
depending on hole conditions, 3500'.  
Cement volumes will be adjusted  
proportionately for depth changes of multi  
stage tool, assumption for tool is water flow.

## 6. Minimum Specifications for Pressure Control

The blowout preventer equipment (BOP) shown in Exhibit #9 will consist of a double ram-type (2000 psi WP) preventer, and in some cases possibly a 2000 psi Hydril type annular preventer as provided for in Onshore Order #2. This unit will be hydraulically operated and the ram type preventer will be equipped with blind rams on top of 4 1/2" drill pipe rams on the bottom. A 13-5/8" or 11" BOP will be used, depending on the rig selected, during the drilling of the well. The BOP will be nipped up on the 13 3/8" surface casing with BOP equipment and tested to 2000 psi. When 11" BOP is used the special drilling flange will be utilized on the 13-3/8" head to allow testing the BOP with a retrievable test plug. After setting 8-5/8" the BOP will then be nipped up on the 8 5/8" intermediate casing and tested by a third party to 2000 psi and used continuously until total depth is reached. Pipe rams will be operationally checked each 24-hour period. Blind rams will be operationally checked on each trip out of the hole. These checks will be noted on the daily tour sheets. Other accessories to the BOP equipment (Exhibit #10) will include a Kelly cock and floor safety valve, choke lines and a choke manifold (Exhibit #11) with a 2000 psi WP rating.

see  
COA

The majority of the rigs currently in use have a 13-5/8" BOP, so no special provision is needed for most wells in the area for conventionally testing the BOP with a test plug. However, due to the vagaries of rig scheduling, it might be that one of the few rigs with 11" BOP's might be called upon to drill any specific well in the area. Note that intermediate hole size is always 11". Therefore, COG Operating LLC respectfully requests a variance to the requirement of 13-5/8" BOP on 13-3/8" casing. When that circumstance is encountered the special flange will be utilized to allow testing the entire BOP with a test plug, without subjecting the casing to test pressure. The special flange also allows the return to full-open capability if desired.

**7. Types and Characteristics of the Proposed Mud System**

The well will be drilled to TD with a combination of brine, cut brine and polymer mud system. The applicable depths and properties of this system are as follows:

DEPTH	TYPE	WEIGHT	VISCOSITY	WATERLOSS
0-650' <del>150</del>	Fresh Water	8.5	28	N.C.
<del>650-2100'</del> <sup>2000</sup>	Brine	10	30	N.C.
2100'-TD	Cut Brine	8.7-9.1	29	N.C.

Sufficient mud materials will be kept at the well site to maintain mud properties and meet minimum lost circulation and weight increase requirements at all times.

**8. Auxiliary Well Control and Monitoring Equipment**

- A. Kelly cock will be kept in the drill string at all times.
- B. A full opening drill pipe-stabbing valve with proper drill pipe connections will be on the rig floor at all times.

**9. Logging, Testing and Coring Program *See COA***

- A. The electric logging program will consist of GR-Dual Laterolog, Spectral Density, Dual Spaced Neutron, CSNG Log and will be run from TD to 8 5/8" casing shoe.
- B. Drill Stem test is not anticipated.
- C. No conventional coring is anticipated.
- D. Further testing procedures will be determined after the 5 1/2" production casing has been cemented at TD, based on drill shows and log evaluation.

**10. Abnormal Conditions, Pressure, Temperatures and Potential Hazards**

No abnormal pressures or temperatures are anticipated. The estimated bottom hole at TD is 110 degrees and the estimated maximum bottom hold pressure is 2300 psig. Measurable gas volumes or Hydrogen Sulfide levels have not been encountered during drilling operations in this area, although a Hydrogen Sulfide Drilling Operation Plan is attached to this program. No major loss of circulation zones has been reported in offsetting wells.

**11. Anticipated Starting Date and Duration of Operations**

Road and location work will not begin until approval has been received from the BLM. As this is a Master Drilling plan, please refer to the Form 3160-3 for the anticipated start date. Once commenced, drilling operations should be finished in approximately 15 days. If the well is productive, an additional 30 days will be required for completion and testing before a decision is made to install permanent facilities.



## COG Operating LLC

Lea County, NM (NAD27 NME)

BC Federal #60

BC Federal #60

OH

RECEIVED

MAR 28 2011

HOBBSUCD

Plan: Plan #1 - 7-7/8" Hole

SHL = 1305' FNL & 915' FWL

BHL = 1660' FNL & 980' FWL

Top of Paddock = 1660' FNL & 980' FWL @ 5375' TVD

## Standard Planning Report

18 November, 2010



Scientific Drilling  
Directional Drilling Operations





Scientific Drilling  
Planning Report



Database: EDM-Julio  
Company: COG Operating LLC  
Project: Lea County, NM (NAD27 NME)  
Site: BC Federal #60  
Well: BC Federal #60  
Wellbore: OH  
Design: Plan #1 - 7-7/8" Hole

Local Co-ordinate Reference: Well BC Federal #60  
TVD Reference: GL Elev. @ 3968.00usft  
MD Reference: GL Elev. @ 3968.00usft  
North Reference: Grid  
Survey Calculation Method: Minimum Curvature

Project: Lea County, NM (NAD27 NME)

Map System: US State Plane 1927 (Exact solution)  
Geo Datum: NAD 1927 (NADCON CONUS)  
Map Zone: New Mexico East 3001

System Datum: Mean Sea Level

Site: BC Federal #60

Site Position: Northing: 663,798.90 usft Latitude: 32° 49' 25.346 N  
From: Map Easting: 665,766.40 usft Longitude: 103° 47' 37.383 W  
Position Uncertainty: 0.00 usft Slot Radius: 13-3/16 " Grid Convergence: 0.29 °

Well: BC Federal #60

Well Position +N/-S 0.00 usft Northing: 663,798.90 usft Latitude: 32° 49' 25.346 N  
+E/-W 0.00 usft Easting: 665,766.40 usft Longitude: 103° 47' 37.383 W  
Position Uncertainty 0.00 usft Wellhead Elevation: Ground Level: 3,968.00 usft

Wellbore: OH

Magnetics	Model Name	Sample Date	Declination (°)	Dip Angle (°)	Field Strength (nT)
	IGRF2010	2010/11/18	7.80	60.72	49,007

Design: Plan #1 - 7-7/8" Hole

Audit Notes:

Version: Phase: PLAN Tie On Depth: 0.00

Vertical Section:	Depth From (TVD) (usft)	+N/-S (usft)	+E/-W (usft)	Direction (°)
	0.00	0.00	0.00	169.33

Plan Sections

Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)	TFO (°)	Target
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
2,200.00	0.00	0.00	2,200.00	0.00	0.00	0.00	0.00	0.00	0.00	
2,565.96	7.32	169.33	2,564.97	-22.94	4.32	2.00	2.00	0.00	169.33	
5,031.12	7.32	169.33	5,010.03	-331.56	62.48	0.00	0.00	0.00	0.00	
5,397.08	0.00	0.00	5,375.00	-354.50	66.80	2.00	-2.00	0.00	180.00	TG1-BC Fed #60
7,122.08	0.00	0.00	7,100.00	-354.50	66.80	0.00	0.00	0.00	0.00	PBHL-BC Fed #60



Scientific Drilling  
Planning Report



Database: EDM-Julio  
Company: COG Operating LLC  
Project: Lea County, NM (NAD27 NME)  
Site: BC Federal #60  
Well: BC Federal #60  
Wellbore: OH  
Design: Plan #1 - 7-7/8" Hole

Local Co-ordinate Reference: Well BC Federal #60  
TVD Reference: GL Elev. @ 3968.00usft  
MD Reference: GL Elev. @ 3968.00usft  
North Reference: Grid  
Survey Calculation Method: Minimum Curvature

Planned Survey

Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
North HL-BC Fed #60 - East HL-BC Fed #60									
2,100.00	0.00	0.00	2,100.00	0.00	0.00	0.00	0.00	0.00	0.00
8-5/8" Casing									
2,200.00	0.00	0.00	2,200.00	0.00	0.00	0.00	0.00	0.00	0.00
KOP Start Build 2.00°/100'									
2,300.00	2.00	169.33	2,299.98	-1.71	0.32	1.75	2.00	2.00	0.00
2,400.00	4.00	169.33	2,399.84	-6.86	1.29	6.98	2.00	2.00	0.00
2,500.00	6.00	169.33	2,499.45	-15.42	2.91	15.69	2.00	2.00	0.00
2,564.96	7.30	169.33	2,563.97	-22.81	4.30	23.22	2.00	2.00	0.00
EOC hold 7.32°									
2,565.96	7.32	169.33	2,564.97	-22.94	4.32	23.34	2.00	2.00	0.00
2,600.00	7.32	169.33	2,598.73	-27.20	5.13	27.68	0.00	0.00	0.00
2,700.00	7.32	169.33	2,697.91	-39.72	7.48	40.42	0.00	0.00	0.00
2,800.00	7.32	169.33	2,797.10	-52.24	9.84	53.16	0.00	0.00	0.00
2,900.00	7.32	169.33	2,896.28	-64.76	12.20	65.90	0.00	0.00	0.00
3,000.00	7.32	169.33	2,995.47	-77.28	14.56	78.64	0.00	0.00	0.00
3,100.00	7.32	169.33	3,094.65	-89.80	16.92	91.38	0.00	0.00	0.00
3,200.00	7.32	169.33	3,193.84	-102.32	19.28	104.12	0.00	0.00	0.00
3,300.00	7.32	169.33	3,293.02	-114.84	21.64	116.86	0.00	0.00	0.00
3,400.00	7.32	169.33	3,392.21	-127.36	24.00	129.60	0.00	0.00	0.00
3,500.00	7.32	169.33	3,491.39	-139.87	26.36	142.34	0.00	0.00	0.00
3,600.00	7.32	169.33	3,590.58	-152.39	28.72	155.08	0.00	0.00	0.00
3,700.00	7.32	169.33	3,689.77	-164.91	31.08	167.82	0.00	0.00	0.00
3,800.00	7.32	169.33	3,788.95	-177.43	33.43	180.56	0.00	0.00	0.00
3,900.00	7.32	169.33	3,888.14	-189.95	35.79	193.30	0.00	0.00	0.00
4,000.00	7.32	169.33	3,987.32	-202.47	38.15	206.04	0.00	0.00	0.00
4,100.00	7.32	169.33	4,086.51	-214.99	40.51	218.77	0.00	0.00	0.00
4,200.00	7.32	169.33	4,185.69	-227.51	42.87	231.51	0.00	0.00	0.00
4,300.00	7.32	169.33	4,284.88	-240.03	45.23	244.25	0.00	0.00	0.00
4,400.00	7.32	169.33	4,384.06	-252.55	47.59	256.99	0.00	0.00	0.00
4,500.00	7.32	169.33	4,483.25	-265.07	49.95	269.73	0.00	0.00	0.00
4,600.00	7.32	169.33	4,582.43	-277.59	52.31	282.47	0.00	0.00	0.00
4,700.00	7.32	169.33	4,681.62	-290.11	54.67	295.21	0.00	0.00	0.00
4,800.00	7.32	169.33	4,780.80	-302.63	57.03	307.95	0.00	0.00	0.00
4,900.00	7.32	169.33	4,879.99	-315.15	59.38	320.69	0.00	0.00	0.00
5,000.00	7.32	169.33	4,979.17	-327.67	61.74	333.43	0.00	0.00	0.00
5,031.12	7.32	169.33	5,010.04	-331.56	62.48	337.40	0.00	0.00	0.00
Start Drop 2.00°/100'									
5,100.00	5.94	169.33	5,078.46	-339.38	63.95	345.35	2.00	-2.00	0.00
5,200.00	3.94	169.33	5,178.08	-347.84	65.55	353.96	2.00	-2.00	0.00
5,300.00	1.94	169.33	5,277.94	-352.88	66.50	359.09	2.00	-2.00	0.00
5,397.08	0.00	169.33	5,375.00	-354.50	66.80	360.74	2.00	-2.00	0.00
EOC hold 0.00° - TG1-BC Fed #60									
7,122.08	0.00	0.00	7,100.00	-354.50	66.80	360.74	0.00	0.00	0.00
PBHL-BC Fed #60									



Scientific Drilling  
Planning Report



Database: EDM-Julio  
Company: COG Operating LLC  
Project: Lea County, NM (NAD27 NME)  
Site: BC Federal #60  
Well: BC Federal #60  
Wellbore: OH  
Design: Plan #1 - 7-7/8" Hole

Local Co-ordinate Reference:  
TVD Reference:  
MD Reference:  
North Reference:  
Survey Calculation Method:  
Well BC Federal #60  
GL Elev. @ 3968.00usft  
GL Elev. @ 3968.00usft  
Grid  
Minimum Curvature

Design Targets

Target Name	hit/miss target Shape	Dip Angle (°)	Dip Dir. (°)	TVD (usft)	+N/-S (usft)	+E/-W (usft)	Northing (usft)	Easting (usft)	Latitude	Longitude
North HL-BC Fed #60	- plan misses target center by 352.96usft at 0.00usft MD (0.00 TVD, 0.00 N, 0.00 E) - Rectangle (sides W100.00 H0.00 D0.00)	0.00	0.00	0.00	-344.50	76.80	663,454.40	665,843.20	32° 49' 21.933 N	103° 47' 36.504 W
East HL-BC Fed #60	- plan misses target center by 352.96usft at 0.00usft MD (0.00 TVD, 0.00 N, 0.00 E) - Rectangle (sides W0.00 H100.00 D0.00)	0.00	0.00	0.00	-344.50	76.80	663,454.40	665,843.20	32° 49' 21.933 N	103° 47' 36.504 W
TG1-BC Fed #60	- plan hits target center - Circle (radius 10.00)	0.00	0.00	5,375.00	-354.50	66.80	663,444.40	665,833.20	32° 49' 21.835 N	103° 47' 36.622 W
PBHL-BC Fed #60	- plan hits target center - Circle (radius 10.00)	0.00	0.00	7,100.00	-354.50	66.80	663,444.40	665,833.20	32° 49' 21.835 N	103° 47' 36.622 W

Casing Points



Measured Depth (usft)	Vertical Depth (usft)	Name	Casing Diameter (")	Hole Diameter (")
2,100.00	2,100.00	8-5/8" Casing	8-5/8	12-1/4

Plan Annotations

Measured Depth (usft)	Vertical Depth (usft)	Local Coordinates		Comment
		+N/-S (usft)	+E/-W (usft)	
2,200.00	2,200.00	0.00	0.00	KOP Start Build 2.00°/100'
2,564.96	2,563.97	-22.81	4.30	EOC hold 7.32°
5,031.12	5,010.04	-331.56	62.48	Start Drop 2.00°/100'
5,397.08	5,375.00	-354.50	66.80	EOC hold 0.00°



Scientific Drilling for COG Operating LLC  
Site: Lea County, NM (NAD27 NME)  
Well: BC Federal #60  
Wellbore: OH  
Design: Plan #1 - 7-7/8" Hole



#### LEGEND

Plan #1 - 7-7/8" Hole

#### WELLBORE TARGET DETAILS (MAP CO-ORDINATES)

Name	TVD	+N/-S	+E/-W	Northing	Easting	Latitude	Longitude	Shape
East HL-BC Fed #60	0.00	-344.50	76.80	663454.40	665843.20	32°49' 21.933 N	103°47' 36.504 W	Rectangle (Sides: L100.00 W0.00)
North HL-BC Fed #60	0.00	-344.50	76.80	663454.40	665843.20	32°49' 21.933 N	103°47' 36.504 W	Rectangle (Sides: L0.00 W100.00)
TG1-BC Fed #60	5375.00	-354.50	66.80	663444.40	665833.20	32°49' 21.835 N	103°47' 36.622 W	Circle (Radius: 10.00)
PBHL-BC Fed #60	7100.00	-354.50	66.80	663444.40	665833.20	32°49' 21.835 N	103°47' 36.622 W	Circle (Radius: 1 0.00)

#### SECTION DETAILS

Sec	MD	Inc	Azi	TVD	+N/-S	+E/-W	Dleg	TFace	Vsect	Target
1	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
2	2200.00	0.00	0.00	2200.00	0.00	0.00	0.00	0.00	0.00	
3	2565.96	7.32	169.33	2564.97	-22.94	4.32	2.00	169.33	23.34	
4	5031.12	7.32	169.33	5010.03	-331.56	62.48	0.00	0.00	337.40	
5	5397.08	0.00	0.00	5375.00	-354.50	66.80	2.00	180.00	360.74	TG1-BC Fed #60
6	7122.08	0.00	0.00	7100.00	-354.50	66.80	0.00	0.00	360.74	PBHL-BC Fed #60

#### WELL DETAILS: BC Federal #60

+N/-S	+E/-W	Northing	Easting	Latitude	Longitude	Slot
0.00	0.00	663798.90	665766.40	32°49' 25.346 N	103°47' 37.383 W	


#### PROJECT DETAILS: Lea County, NM (NAD27 NME)

Plan: Plan #1 - 7-7/8" Hole (BC Federal #60/OH)

Geodetic System: US State Plane 1927 (Exact solution)  
Datum: NAD 1927 (NADCON CONUS)  
Ellipsoid: Clarke 1866  
Zone: New Mexico East 3001  
System Datum: Mean Sea Level

Created By: Julio Pina  
Checked: \_\_\_\_\_  
Reviewed: \_\_\_\_\_  
Approved: \_\_\_\_\_

Date: 18-Nov-10  
Date: \_\_\_\_\_  
Date: \_\_\_\_\_  
Date: \_\_\_\_\_



310 x 250

Not To Scale

Exhibit #6

COG OPERATING LLC  
Rig Layout-Closed Loop  
System

# COG Operating LLC


Exhibit #9

## BOPE and Choke Schematic

**RECEIVED**


MAR 28 2011

HOBBSOCD




Minimum 4" Nominal choke and kill lines

Choke Manifold Requirement (2000 psi WP)  
No Annular Required



**NOTES REGARDING THE BLOWOUT PREVENTERS**  
**Master Drilling Plan**  
**Eddy County, New Mexico**

1. Drilling nipple to be so constructed that it can be removed without use of a welder through rotary table opening, with minimum I.D. equal to preventer bore.
2. Wear ring to be properly installed in head.
3. Blow out preventer and all fittings must be in good condition, 2000 psi WP minimum.
4. All fittings to be flanged.
5. Safety valve must be available on rig floor at all times with proper connections, valve to be full 2000 psi WP minimum.
6. All choke and fill lines to be securely anchored especially ends of choke lines.
7. Equipment through which bit must pass shall be at least as large as the diameter of the casing being drilled through.
8. Kelly cock on Kelly.
9. Extension wrenches and hands wheels to be properly installed.
10. Blow out preventer control to be located as close to driller's position as feasible.
11. Blow out preventer closing equipment to include minimum 40-gallon accumulator, two independent sources of pump power on each closing unit installation all API specifications.



**Exhibit #6**

Not To Scale

COG OPERATING LLC  
Rig Layout-Closed Loop  
Interim reclamation plat