

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

SUBMIT IN TRIPlicate
(Other instructions
verse side)

Budget Bureau No. 1004-0135
Expires August 31, 1985

5. LEASE DESIGNATION AND SERIAL NO.

NM 0127905

6. IF INDIAN, ALLOTTEE OR TRIBE NAME

7. UNIT AGREEMENT NAME

8. FARM OR LEASE NAME

Morton-Federal

9. WELL NO.

10. FIELD AND POOL OR WILDCAT

Vada Penn
11. SEC., T., R., M., OR BLK. AND
SURVEY OR AREA

Section 12, T-9-S, R-35-E

12. COUNTY OR PARISH 13. STATE

Lea New Mexico

SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir.
Use "APPLICATION FOR PERMIT" for such proposals.)

1. OIL WELL ☒ GAS WELL ☐ OTHER ☐

2. NAME OF OPERATOR

M & G Oil Company

3. ADDRESS OF OPERATOR

P.O. Box 766, Tatum NM 88267

4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements.
See also space 17 below.)
At surface

660' FNL & 660'

14. PERMIT NO.

15. ELEVATIONS (Show whether DF, RT, GR, etc.)

4145 GL

18. Check Appropriate Box To Indicate Nature of Notice, Report, or Other Data

NOTICE OF INTENTION TO:

TEST WATER SHUT-OFF

FRACTURE TREAT

SHOOT OR ACIDIZE

REPAIR WELL

(Other)

PULL OR ALTER CASING

MULTIPLE COMPLETE

ABANDON*

CHANGE PLANS

SJS

SUBSEQUENT REPORT OF:

WATER SHUT-OFF

FRACTURE TREATMENT

SHOOTING OR ACIDIZING

(Other)

REPAIRING WELL

ALTERING CASING

ABANDONMENT

Temp

X

(NOTE: Report results of multiple completion on Well
Completion or Recompletion Report and Log form.)

17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any
proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones perti-
nent to this work.)

4-13-87

Moved in and rigged up PBCP Service, Inc. at 7:30 A.M. Ran 5 1/2" (4 5/8" OD) gauge ring on sand line in 5 1/2" casing to 9739'. Pulled out of hole with gaug ring. Ran 5 1/2" Titan Bridge plug on sand line and set at 9739'. Pumped 250 barrels of water. Casing did not load. Ran sinker bar on sand line. Tagged top of bridge plug at original setting point. Measured out of hole with depthometer. Showed bridge to be 50' deeper than original depth by depthometer measurement. Ran second bridge plug on sand line and set 100' higher at 9639' depth by depthometer measurement. Made 2 runs with dump bailer spotting 35' cement plug on top of bridge plug. Shut down for the night at 5:00 P.M.

4-14-87

Loaded casing with 225 BFW. Pressure tested 5 1/2" casing to 500#. Held O.K. Test witnessed by Mr. R.G. Dillow with BLM from Hobbs. Rigged down PBCP Service, Inc. at 8:30 A.M.

~~FINAL REPORT~~

APPROVED FOR 12 MONTH PERIOD

ENDING 6/26/88

18. I hereby certify that the foregoing is true and correct

SIGNED *John Cherry*

TITLE Agent

DATE 6-19-87

(This space for Federal or State office use)

APPROVED BY
CONDITIONS OF APPROVAL, IF ANY:

TITLE

ACCEPTED FOR RECORD

SJS
JUN 25 1987

*See Instructions on Reverse Side

CARLSBAD, NEW MEXICO