



This is to be 3000 psi wp, which is adequate, that will be used on the 11" and 7 7/8" hole. This is the minimum possible BOP stack that will be used. Tenneco may choose to use more equipment and higher pressure.

STATE SG 25 No. 1
Section 25 T10S, R32E, Lea Co., New Mexico