

UNITED STATES DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT
HOBBS, NEW MEXICO 88240

Expires August 31, 1985
5. LEASE DESIGNATION AND SERIAL
Hayes Federal Nm 3586
6. IF INDIAN, ALLOTTEE OR TRIBE NAME

SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir.
Use "APPLICATION FOR PERMIT" for such proposals.)

1. OIL WELL ☒ GAS WELL ☐ OTHER ☐	7. UNIT AGREEMENT NAME Hayes Federal
2. NAME OF OPERATOR M & W of Lovington, Inc.	8. FARM OR LEASE NAME 2
3. ADDRESS OF OPERATOR Box 922, Lovington, NM 88260	9. WELL NO. Allison Penn
4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements. See also space 17 below.) At surface 660' FSL & 660' FEL <i>Unit P</i>	10. FIELD AND POOL, OR WILDCAT Unit P, Sec. 30, T-8S, R-37E
14. PERMIT NO.	15. ELEVATIONS (Show whether DF, RT, GR, etc.)
12. COUNTY OR PARISH Roosevelt	13. STATE New Mexico

16. Check Appropriate Box To Indicate Nature of Notice, Report, or Other Data

NOTICE OF INTENTION TO:		SUBSEQUENT REPORT OF:	
TEST WATER SHUT-OFF	☐	WATER SHUT-OFF	☐
FRACURE TREAT	☐	FRACURE TREATMENT	☐
SHOOT OR ACIDIZE	☐	SHOOTING OR ACIDIZING	☐
REPAIR WELL	☐	(Other)	☐
PULL OR ALTER CASING	☐	REPAIRING WELL	☐
MULTIPLE COMPLETION	☐	ALTERING CASING	☐
ABANDON*	☒	ABANDONMENT*	☐
CHANGE PLANS	☐		

(NOTE: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.) *

1. T.I.H. with tubing & 8-5/8" cement retainer & set at 4100'.
2. Pump 300 bbls. of water to establish rate.
3. Pump 725 sks. cement and squeeze well from 4100' to T.D. This leaves 55' of cement into 8-5/8" casing. Tag plug.
4. Set plug at ~~500'~~ ^{410'-310'} (100' plug) Tag plug.
5. Plug surface. *Minimum 50' cement plug.*
6. Work to begin before June 1, 1992.

18. I hereby certify that the foregoing is true and correct

SIGNED *Garden Murphy*

TITLE Vice President

DATE 12/23/91


(This space for Federal or State office use)

APPROVED BY

TITLE

DATE

CONDITIONS OF APPROVAL, IF ANY: *As modified*



*See Instructions on Reverse Side