

27000-5  
Mar 31 0 49 AM '85

5. Minimum Specifications for Pressure Control:

The blowout preventer equipment (BOP) shown in Exhibit "A" will consist of a double ram-type (3000 psi WP) preventer and a bag-type (hydril) preventer (3000 psi WP). Both units will be hydraulically operated and the ram-type preventer will be equipped with blind rams on top and 4 1/2" drill pipe rams on bottom. Both BOP's will be nipped up on the 8 5/8" surface casing and used continuously until TD is reached.

Pipe rams will be operationally checked each 24 hour period. Blind rams will be operationally checked on each trip out of the hole. These checks will be noted on the daily tour sheets. A 2" kill line and 3" choke line will be included in the drilling spool located below the ram-type BOP. Other accessories to the BOP equipment will include a kelly cock and floor safety valve (inside BOP) and choke lines and choke manifold with 3000 psi WP rating.

6. Types and Characteristics of the Proposed Mud System:

0' to 4803'      Brine and fresh water with salt gel and starch will be used to maintain a viscosity of approximately 30, MW 9.5, Ph 10, and a water loss of less than 15.

Sufficient mud materials to maintain mud properties and meet minimum lost circulation and weight increase requirements will be kept at the wellsite at all times.

7. Auxiliary Well Control and Monitoring Equipment:

- A. A kelly cock will be kept in the drill string at all times.
- B. A full opening drill pipe stabbing valve (inside BOP) with proper drill pipe connections will be on the rig floor at all times.

8. Testing, Logging and Coring Program:

No cores or tests are anticipated. A cased hole correlation log will be run after 5 1/2" casing is run.