

NM-0384

SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir.
Use "APPLICATION FOR PERMIT—" for such proposals.)

1. OIL WELL ☒ GAS WELL ☐ OTHER ☐	
2. NAME OF OPERATOR Northland Operating Co. 30-065-00886	3a. Area Code & Phone No. 214-521-9959
3. ADDRESS OF OPERATOR 3500 Oak Lawn, Suite 380, LB# 31, Dallas, Texas 75219-4398	
4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements.* See also space 17 below.) At surface Sec. 27 Unit G 1650' FNL 1650' FEL, T 13S, R31E	
14. PERMIT NO.	15. ELEVATIONS (Show whether DF, RT, OR, etc.) DF 4407'

7. UNIT AGREEMENT NAME Rock Queen Unit Sec 27	
8. FARM OR LEASE NAME	
9. WELL NO. 27-7	
10. FIELD AND POOL, OR WILDCAT Caprock Queen	
11. SEC., T., R., M., OR BLK. AND SURVEY OR AREA 27-13S-31E Section 27	
12. COUNTY OR PARISH Chaves	13. STATE NM

16. Check Appropriate Box To Indicate Nature of Notice, Report, or Other Data

NOTICE OF INTENTION TO:

TEST WATER SHUT-OFF

PULL OR ALTER CASING

FRACTURE TREAT

MULTIPLE COMPLETE

SHOOT OR ACIDIZE

ABANDON*

REPAIR WELL

CHANGE PLANE

(Other) Return to Production

XX

SUBSEQUENT REPORT OF:

WATER SHUT-OFF

FRACTURE TREATMENT

SHOOTING OR ACIDIZING

(Other)

REPAIRING WELL


ALTERING CASING

ABANDONMENT*

(Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*

Run tbg., rods & pump to 3000'. Lay flowline and connect to electricity.
Estimate start of work 10/21/96.



18. I hereby certify that the foregoing is true and correct

SIGNED

TITLE

Vice President

Date

10/16/96

(This space for Federal or State office use)

APPROVED BY

TITLE

Date

CONDITIONS OF APPROVAL, IF ANY:

Subject

UNIT R-1 QUEEN FIELD ADROCK
 WELL 27G (27-7) LOC 135 31E 27G
 CURRENT STATUS T.A. PRODUCER

Date

Sheet of

Project No.

By

MEAS. DATUM: 4415 DF
 K B ELEV: 4415 GR. ELEV: 4407

32.3 #/FT 8 5/8" CSA 315'
 w/1455 x cmt

VISUAL INSPECTION 7/24/96 SHOWED
 5 1/2" x 2" SWAGE ON WELL HEAD.
 NO TUBING IN WELL, NO ELEC POWER
 AT WELL. HAD 2" VALVE ON TOP
 OF SWAGE.

2 3/8" tbg
 3/4" rods
 1.5" dia pmp

TOP QUEEN SAND @ 3016'

I (1) (1) 7-1-SS ORIG. COMP. THRU
 PERFS 3023-3027'.
 1PF:456 BPLODD, NATURAL
 35°API

15.5 #/FT 5 1/2" CSA 3034'
 w/1005 x cmt.

TD 3034'

LAST PROD: AUGUST, 1968. SI
 DUE TO HIGH WATER CUT.
 DISCONTINUED TO PRODUCE
 ± 4 BOPD.