

6. SOURCE OF CONSTRUCTION MATERIALS.

- A. Any caliche required for construction of the drilling pad and the new access road, as well as for any resurfacing of the existing access road, will be obtained from an existing federally-owned pit in the NE/NE corner of Section 4-T9S-R30E, approximately one mile from the location.

7. METHODS OF HANDLING WASTE DISPOSAL.

- A. Drill cuttings will be disposed of in the reserve pits.
- B. Drilling fluids will be allowed to evaporate in the reserve pits until the pits are dry.
- C. Water produced during operations will be collected in tanks until hauled to an approved disposal system, or separate disposal application will be submitted to the U.S.G.S. for appropriate approval.
- D. Oil produced during operations will be stored in tanks until sold.
- E. Current laws and regulations pertaining to the disposal of human waste will be complied with.
- F. Trash, waste paper, garbage and junk will be buried in a separate trash pit and covered with a minimum of 24 inches of dirt. All waste materials will be contained to prevent scattering by the wind.
- G. All trash and debris will be buried or removed from the wellsite within 30 days after finishing drilling and/or completion operations.

8. ANCILLARY FACILITIES.

- A. None required.

9. WELLSITE LAYOUT.

- A. Exhibit C shows the relative location and dimensions of the well pad, reserve pits, and major rig components.
- B. Relatively little leveling will be required to construct the location. The ground surface at the wellsite is relatively flat, with only very minor anomalies. Little, if any, caliche will be required to construct the pad or the new road.
- C. There are no plans to line the earthen reserve pit since it should seal quite rapidly with drill solids and bentonite. Water used for drilling is of discharge quality.
- D. The pad and pit area has been staked and flagged.

10. PLANS FOR RESTORATION OF THE SURFACE.

- A. After finishing drilling and/or completion operations, all equipment and other material not needed for further operations will be removed.

RECEIVED

JUL 17 1977

U.S. CONSERVATION COMM.
WASDC, D. C.