

APPLICATION FOR DRILLING PERMIT

Page -2-

8. Testing, coring and logging program:
 - A. No DST's are anticipated.
 - B. No coring is anticipated.
 - C. Compensated Density, Laterlog w/Gamma Ray Logs will be run from surface pipe shoe to total depth.
9. No abnormally pressured zones have been encountered in wells drilled to the east or west and thus are not expected at this location.
10. The anticipated starting date is January 15, 1980.