

SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir. Use Form 9-331-C for such proposals.)

1. oil ☐ well gas ☒ well other ☐
2. NAME OF OPERATOR
DEPCO, Inc.
3. ADDRESS OF OPERATOR
800 Central, Odessa, TX 79761
4. LOCATION OF WELL (REPORT LOCATION CLEARLY. See space 17 below.) F-1980 FN&WL, SEC. 8, T-13-S,
AT SURFACE: R-30-E
AT TOP PROD. INTERVAL:
AT TOTAL DEPTH:
16. CHECK APPROPRIATE BOX TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

REQUEST FOR APPROVAL TO:

- TEST WATER SHUT-OFF ☐
FRACTURE TREAT ☐
SHOOT OR ACIDIZE ☐
REPAIR WELL ☐
PULL OR ALTER CASING ☐
MULTIPLE COMPLETE ☐
CHANGE ZONES ☐
ABANDON* ☐
(other) ☐

SUBSEQUENT REPORT OF:

- ☐
☐
☐
☐
☐
☐
☐
☒

RECEIVED

MAY 13 1983

EX. 8-331

5. LEASE
NM 21503
6. IF INDIAN, ALLOTTEE OR TRIBE NAME
7. UNIT AGREEMENT NAME
8. FARM OR LEASE NAME
WHITE RANCH UNIT
9. WELL NO.
1
10. FIELD OR WILDCAT NAME
WHITE RANCH ATOKA
11. SEC., T., R., M., OR BLK. AND SURVEY OR AREA
SEC. 8, 13, 30
12. COUNTY OR PARISH
CHAVES
13. STATE
NEW MEXICO
14. API NO.
15. ELEVATIONS (SHOW DF, KDB, AND WD)
3851 CR

(NOTE: Report results of multiple completion or zone change on Form 9-330.)

17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*

5-2-83: Pulled tbg. & pkr. Ran retainer to 9275'. Pumped 50 sxs into perfs @ 9312-26'. Set 25 sx plug on top of retainer.

5-3-83: Set 150' plug from 7270-7420'. Set 100' plug from 3900-4000'. Set 100' plug from 2550-2650'. Set 100' plug from 1400-1500'.


5-4-83: Cut off wellhead. Ran 1" between 8 5/8" & 13 3/8" csg. spotted 100' plug from 290-391'. Spotted 60' plug @ surface. Spotted 60' plug between 8 5/8" & 4 1/2" @ surface. Spotted 60' plug inside 4 1/2" @ surface. Set dry hole marker & released rig.

Subsurface Safety Valve: Manu. and Type _____ Set @ _____ Ft.

18. I hereby certify that the foregoing is true and correct

SIGNED R.L. Denney R.L. Denney TITLE Chief Prod. Clerk DATE 5-12-83

APPROVED BY PETER W. CHESTER TITLE _____ DATE _____
CONDITIONS OF APPROVAL, IF ANY:



See Instructions on Reverse Side

ACCEPTED FOR RECORD

SEP 12 1983

ROSWELL, NEW MEXICO