

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

N. M. OIL CONS. COMMISSION
P. O. BOX 1980
HOBBS, NEW MEXICO 88240

FORM APPROVED
Budget Bureau No. 1004-0135
Expires: March 31, 1993

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to deepen or reentry to a different reservoir.
Use "APPLICATION FOR PERMIT—" for such proposals

SUBMIT IN TRIPLICATE

1. Type of Well

☒ Oil Well ☐ Gas Well ☐ Other

2. Name of Operator

Petroleum Development Corporation

3. Address and Telephone No.

9720-B Candelaria NE, Albuquerque, NM 87112

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

643' FNL, 782' FEL
Section 7, T8S, R31E

5. Lease Designation and Serial No.

NM-15016

6. If Indian, Allottee or Tribe Name

7. If Unit or CA, Agreement Designation

8. Well Name and No.

Wattam Federal

9. API Well No.


6

10. Field and Pool, or Exploratory Area

Cato

11. County or Parish, State

Chaves County, New Mex



12. CHECK APPROPRIATE BOX(s) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION

- ☐ Notice of Intent
☒ Subsequent Report
☐ Final Abandonment Notice

TYPE OF ACTION

- ☐ Abandonment
☒ Recompletion
☐ Plugging Back
☐ Casing Repair
☐ Altering Casing
☐ Other Horizontal
☐ Change of Plans
☐ New Construction
☐ Non-Routine Fracturing
☐ Water Shut-Off
☐ Conversion to Injection
☐ Dispose Water

(Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*

- 1) MIRUPU and Drilling Equipment.
- 2) Drill cement plugs: surface to 410', 1231'-1370', 3500'-3546' & CIBP @ 3546'.
- 3) Set cement retainer @ 3695'. Perforations 3708'-3794' & 3642'-3682', communicated.
Set packer @ 3369'. Cement squeeze perforations w/250 sx. cement.
- 4) Drill cement 3450' to 3695'.
- 5) Mill casing from 3470'-3544'.
- 6) Spot 45 sx. cement plug. Reverse out @ 3356'.
- 7) Drill cement 3440'-3520'.
- 8) Drill horizontal Arc 3520' to 3840'. TVD-3720'.
- 9) Drilled horizontal lateral to 5371'. TVD-3711.3'. 1096.6' FNL, 2448.8' FEL
- 10) Acidized w/15,000 gal. 15% NEFE acid.
- 11) Put well on pump.

14. I hereby certify that the foregoing is true and correct

Signed

J.C. Johnson

Title


President

(This space for Federal or State office use)

Approved by

Title

Conditions of approval, if any:



Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statement or representations as to any matter within its jurisdiction.

*See Instruction on Reverse Side

