

A mudlogging trailer will be placed on the well from the base of intermediate casing to total depth.

A conventional 4" dia-30' core will be cut thru the Abo pay.

7. Auxiliary Equipment: A Kelly cock will be installed on the rig floor while drilling operations are in progress.

8. Proposed Mud Program:

NC
450' 0' - 400' 450' Fresh water mud.
450' 400' - 2900' Brine water.
2900' - 6200' Fresh water added to existing fluids.
6200' - TD Cut Brine water, salt gel, starch drilling fluid with 5% oil.

9. Potential Hazards: No abnormal pressure or temperature zones are anticipated.

10. Anticipated Starting Date: Drilling operations will commence before July 12, 1987. Completion operations will begin immediately after drilling is completed.

RECEIVED
JUL 17 1987
OCD
HOBBS OFFICE