

Culp Ranch #3  
Supplemental Drilling Data  
Page 3:

9. ABNORMAL PRESSURES, TEMPERATURES OR HYDROGEN SULFIDE GAS:

None anticipated. Based on other offset wells, bottomhole pressure at TD is expected to be 4000 psi with a bottomhole temperature of 170 degrees.

The BLM was contacted regarding known H<sub>2</sub>S occurrences. None have been encountered in this area.

10. ANTICIPATED STARTING DATE:

Drilling operations should begin within 30 days after approval of this application. Drilling and completion operations should be completed within 60 days after spudding.

