

8. ANCILLARY FACILITIES

No facilities will be constructed at this time.

9. WELLSITE LAYOUT

- A. Exhibit "F" shows the proposed wellsite layout.
- B. Reserve pits and trailer locations are as indicated
- C. Earthen pits (reserve pit) excavated below pad grade will be used for final separation of suspended drill cuttings.
- D. Pits are to be lined with a plastic liner which will extend beyond the crest a minimum of 2 ft. and will be anchored with earth in the standard industry practice.
- E. The reserve pit will be fenced on three sides with a four strand barbwire fence during drilling and completion; after drilling operations cease the remaining side will be fenced. The fence will be removed when the reserve pit is backfilled.
- F. A birdproof netting will be maintained over the reserve pit immediately following the cessation of drilling operations and remaining until the pit is backfilled.

10. SURFACE RESTORATION

- A. Rehabilitation and restoration of the location and reserve pit will start in a timely manner upon the cessation of drilling operations.
- B. The reserve pit shall be allowed to dry, and then backfilled. The area will be leveled and reshaped to eliminate erosion while maintaining the general topography of the preconstruction landform. Revegetation will be in accordance with landowner request and BLM recommendations.
- C. Wellpad and access road will be recontoured and revegetated according to landowner request and BLM recommendations in effect at the time of plugging the well.

11. OTHER INFORMATION

- A. Cultural Resources

Subsequent to performing a Class I Cultural Resource Investigation, a Class III Cultural Resource

