


DUPLICATE

NEW MEXICO OIL CONSERVATION COMMISSION  
Santa Fe, New Mexico



MISCELLANEOUS NOTICES

Submit this notice in TRIPLICATE to the District Office, Oil Conservation Commission, before the work specified is to begin. A copy will be returned to the sender on which will be given the approval, with any modifications considered advisable, or the rejection by the Commission or agent, of the plan submitted. The plan as approved should be followed, and work should not begin until approval is obtained. See additional instructions in the Rules and Regulations of the Commission.

Indicate Nature of Notice by Checking Below

NOTICE OF INTENTION TO CHANGE PLANS		NOTICE OF INTENTION TO TEMPORARILY ABANDON WELL		NOTICE OF INTENTION TO DRILL DEEPER	
NOTICE OF INTENTION TO PLUG WELL	<b>X</b>	NOTICE OF INTENTION TO PLUG BACK		NOTICE OF INTENTION TO SET LINER	
NOTICE OF INTENTION TO SQUEEZE		NOTICE OF INTENTION TO ACIDIZE		NOTICE OF INTENTION TO SHOOT (Nitro)	
NOTICE OF INTENTION TO GUN PERFORATE		NOTICE OF INTENTION (OTHER)		NOTICE OF INTENTION (OTHER)	

OIL CONSERVATION COMMISSION  
SANTA FE, NEW MEXICO

Odessa, Texas  
(Place)

January 2, 1954  
(Date)

Gentlemen:

Following is a Notice of Intention to do certain work as described below at the Forest Oil Corporation & Houston Oil Company, et al H.L. Lawe, et al Well No. 2 in L (Unit) (Company or Operator)  
NW 1/4 SW 1/4 of Sec. 25, T. -13-S, R. 37-E, NMPM., King-Wolfcamp Pool  
(40-acre Subdivision)  
Lee County.

FULL DETAILS OF PROPOSED PLAN OF WORK  
(FOLLOW INSTRUCTIONS IN THE RULES AND REGULATIONS)

This well was drilled to a total depth of 10,240' into Wolfcamp formation on 12-31-53. Drill stem tests at 9769'-9808'; 10,030'-61'; 10,120'-40' and 10,155'-85' recovered only drilling mud very slightly oil & gas out and sulphur water.

On January 2, 1954 verbal approval to plug and abandon was given by Mr. Stanley J. Stanley, Engineer. The following procedure was proposed: With hole filled with heavy drilling mud, cement plugs would be placed from 9628'-9760', 132' plug, and from 4572'-4675' a 103' plug. An attempt to recover 9 5/8" above 2175' to be made, a 35' plug to be placed at point of separation. A 9 1/2" plug to be placed from 223'-313' and 26' in the top of 13 3/8" casing on the top of which a 1/2" steel plate would be welded with 4 1/2" steel marker extended 4' above ground level.

Approved JAN 8 1954, 19\_\_\_\_  
Except as follows:

Approved  
OIL CONSERVATION COMMISSION

By J. G. Stanley  
Engineer District 1  
Title \_\_\_\_\_

Forest Oil Corporation  
Company or Operator

By J. R. Wright  
Position District Production Superintendent  
Send Communications regarding well to:

Name R.E. Warner  
Address 1229 Milan Bldg. San Antonio, Texas

