

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

N.M. Oil Cons. Division
P.O. Box 1980
Hobbs, NM 88241

FORM APPROVED
Budget Bureau No. 1004-0135
Expires: March 31, 1993

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to deepen or reentry to a different reservoir.
Use "APPLICATION FOR PERMIT-" for such proposals

SUBMIT IN TRIPLICATE

1. Type of Well

☒ Oil Well ☐ Gas Well ☐ Other

2. Name of Operator

Apache Corporation

3. Address and Telephone No.

2000 Post Oak Blvd., Ste. 100, Houston, Texas 77056-4400 / 713-296-6000

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

1650' FSL & 660' FEL Unit I, Sec. 35, T13S, R33E

5. Lease Designation and Serial No.

NM01124

6. If Indian, Allottee or Tribe Name

7. If Unit or CA, Agreement Designation

8. Well Name and No.

Willard Beaty # 05

9. API Well No.

30-025-22010

10. Field and Pool, or Exploratory Area

Lazy J Penn

11. County or Parish, State

Lea County, NM

12. CHECK APPROPRIATE BOX(s) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION

TYPE OF ACTION

- ☒ Notice of Intent
☐ Subsequent Report
☐ Final Abandonment Notice

- ☒ Abandonment
☐ Recompletion
☐ Plugging Back
☐ Casing Repair
☐ Altering Casing
☐ Other

- ☐ Change of Plans
☐ New Construction
☐ Non-Routine Fracturing
☐ Water Shut-Off
☐ Conversion to Injection
☐ Dispose Water

(Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form)

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*

Set CIBP @ 9650' w / 35' of cement on top (7 sx)
Pull approximately 7200' of 5" casing
Cement plug 7250' - 7150' w / 50 sx
Cement plug 4250' - 4150' w / 50 sx
Perf 8-5/8" casing @ 2792' and cement squeeze behind casing w / 925 sx (Circulate cement to surface)
Cement plug 2450' - 2350' w / 50 sx
Cement plug 1150' - 1050' w / 50 sx
Cement plug 420' - 320' w / 50 sx
Cement plug 30' - 0' w / 15 sx
Cement Steel Marker (4" diameter) at least 4' above mean ground level and mark plate w / Apache Corp
Willard Beaty No. 5, Sec. 35, T13S, R33E

RECEIVED
1999 JAN 21 A 10:23
BUREAU OF LAND MGMT.
1000 N. MEXICO AVE
HOBBS, NM 88241

14. I hereby certify that the foregoing is true and correct

Signed

David R. Glass

Title Engineering Technician

Date 1/13/99

(This space for Federal or State office use)

(ORIG. SGD.) DAVID R. GLASS

Approved by

Title

PETROLEUM ENGINEER

Date

FEB 03 1999

Conditions of approval, if any:

Title 18 U.S. C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

*See Instruction on Reverse Side


SEE ATTACHED FOR
CONDITIONS OF APPROVAL

EC
GNW

RECEIVED
JAN 25 99
BLK
ROSWELL, NM
JAN 25 99

Willard Beaty # 5
Lazy J (Penn) Field
API No.: 30-025-22010
1650' FSL & 660' FEL
Sec 35, T13S, R33E
Lea County, New Mexico
Elevation: 4197' (GR)

CURRENT COMPLETION



P & A PROPOSAL

