

State Land 76 No. 1
LEA COUNTY

6. IF WELL CAPABLE OF FLOWING, RIG UP SLICK LINE UNIT & LUBRICATOR. SET TYPE 'N' BLANK PLUG IN PKR. RLSE OVERSHOT AND DISPLACE BACKSIDE W/2% KCL FRSH WTR CONTAINING 10 GAL/100 BBLS TRETOLITE KW-79. LATCH PKR. ND BOP. NU WH. FISH BLANKING PLUG. SWAB WELL BACK TO RESUME PRODUCTION.
7. IF WELL INITIALLY REQUIRES ARTIFICIAL LIFT, RLSE PKR, LWR THRU PERFS & POH STANDING BACK.
8. RIH W/ 31' BP MUD ANCHOR, PERF SUB, SN, 2 JTS 2-7/8" TBG & TAC ON 2-7/8", 6.5#, L-80 PROD TBG. TS $\pm 9450'$, MA $\pm 9508'$, PS $\pm 9504'$, SN $\pm 9503'$, TAC $\pm 9441'$.
9. ND BOP. NU WH. RIH W/ 2-1/2x1.50x24' RHBC ROD PUMP ON 86 TAPER "KD" ROD STRING (167 - 3/4", 106 - 7/8", 107 - 1"). SPACE OUT AS NECESSARY. RLSE RIG.
10. PUT ON PRODUCTION TEST @ 1.50x149x8 = 239 BPD PUMP CAPACITY (CURRENT UNIT SETTING).