

GL@ 4130'

12-1/4" hole
8-5/8" O.D., 24#/ft., @ 400'
400 sx., cement circulated

Rustler @ 1502' (+2743)

Yates @ 2795' (+1346)

Queen @ 3802' (+339')

2-3/8" O.D., 4.7#/ft., J-55, EUE
tubing, plastic lined

Baker AD-1 tension packer @ 4300'

Grayburg @ 4310' (-169')

Perforations (2 JSPP)

4432' - 4437'
4469' - 4476'
4526' - 4531'
4569' - 4572'
4578' - 4582'

San Andres @ 4600' (-459')

PTD 4689'

7-7/8" hole

TD 4705'

4-1/2" O.D., 11.6#/ft., @ 4705'
850 sx., cement circulated

X X X X
X X X X
X X X X

Proposed Completion for Water Injection

NO.	REVISION	BY	DATE	CHKD	APP'D
FOR BIDS	 PHILLIPS PETROLEUM COMPANY BARTLESVILLE, OKLAHOMA			JA NO.	FILE CODE
FOR APPR				AFE NO.	SCALE
FOR CONST	PHILLIPS 'E' STATE WELL NO. 30 Unit letter L, 1980' FSL, 460' FWL, Sec. 13, T-17-S, R-33-E, Lea Co., N.M.			DWG NO.	
DRAWN				SH NO.	
CHECKED					
APP'D					