

Submit 3 Copies
to Appropriate
District Office

State of New Mexico
Energy, Minerals and Natural Resources Department

Form C-103
Revised 1-1-89

DISTRICT I
P.O. Box 1980, Hobbs NM 88240

DISTRICT II
P.O. Drawer DD, Artesia, NM 88210

DISTRICT III
1000 Rio Brazos Rd., Aztec, NM 87410

OIL CONSERVATION DIVISION

P.O. Box 2088
Santa Fe, New Mexico 87504-2088

WELL API NO.	30-025-33185
5. Indicate Type of Lease	STATE <input checked="" type="checkbox"/> FEE <input type="checkbox"/>
6. State Oil & Gas Lease No.	B-2148
7. Lease Name or Unit Agreement Name	LEAMEX
8. Well No.	57
9. Pool name or Wildcat	WILDCAT - MORROW

SUNDRY NOTICES AND REPORTS ON WELLS (DO NOT USE THIS FORM FOR PROPOSALS TO DRILL OR TO DEEPEN OR PLUG BACK TO A DIFFERENT RESERVOIR. USE "APPLICATION FOR PERMIT" (FORM C-101) FOR SUCH PROPOSALS.)	
1. Type of Well: OIL WELL <input checked="" type="checkbox"/> GAS WELL <input type="checkbox"/> OTHER	
2. Name of Operator Phillips Petroleum Company	
3. Address of Operator 4001 Penbrook Street, Odessa, TX 79762	
4. Well Location Unit Letter M : 460 Feet From The SOUTH Line and 905 Feet From The WEST Line Section 16 Township T-17-S Range R-33-E NMPM LEA County	
10. Elevation (Show whether DF, RKB, RT, GR, etc.) 4193' GL	

11. Check Appropriate Box to Indicate Nature of Notice, Report, or Other Data

NOTICE OF INTENTION TO:

PERFORM REMEDIAL WORK ☐ PLUG AND ABANDON ☐
TEMPORARILY ABANDON ☐ CHANGE PLANS ☐
PULL OR ALTER CASING ☐
OTHER: ☐

SUBSEQUENT REPORT OF:

REMEDIAL WORK ☐ ALTERING CASING ☐
COMMENCE DRILLING OPNS. ☐ PLUG AND ABANDONMENT ☐
CASING TEST AND CEMENT JOB ☐
OTHER: SET CEMENT PLUG, TEST MORROW/WOLFCAMP ☒

12. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work) SEE RULE 1103.

02/26/96 CIRC, NOTIFIED NMOCD (GARY WINK) 9:00 AM, 2/26/96 OF INTENT TO ABANDON SILURIAN & TEST UPHOLE TO MORROW. IF UNSUCCESSFUL WILL ABANDON MORROW PER NMOCD INSTURCTIONS AND TEST WOLFCAMP.
LD 3JTS DRILLPIPE, BOTTOM OF DP @ 14,900', PUMPED BALANCED PLUG #1, 14,900'-14,715' W/150 SXS CLASS "H" CMT W/.3% HR-7, 1/2# FLOCELE, 4# GILSONITE, PULLED UPHOLE, WOC, RIH W/DP TAGGED TOC CMT PLUG #1 @ 14,715', PULLED UPHOLE TO 14,400', PUMPED PLUG #2, 14,400'-13900' W/150 SXS CLASS "H" CMT W/.3% HR-7, 1/2# FLOCELE, 4# GILSONITE, TOOH/LDDP.
NOTE: WILL SET 5-1/2", 20# & 17#, CSG @ 13,850' AND CMT IN 2 STAGES WITH A TOTAL OF 1695 SXS CMT WITH TOC AT APPOX. 9,000'
TEST MORROW AND IF UNSUCCESSFUL WILL TEST LEAMEX-WOLFCAMP.

I hereby certify that the information above is true and complete to the best of my knowledge and belief.

SIGNATURE Larry M. Sanders TITLE Senior Regulation Analyst DATE 02/27/96


TYPE OR PRINT NAME Larry M. Sanders TELEPHONE NO. (915)368-1488

(This space for State Use)

ORIGINAL SIGNED BY JERRY SEXTON

APPROVED BY DISTRICT I SUPERVISOR TITLE DATE FEB 29 1996

CONDITIONS OF APPROVAL, IF ANY:



100 100 100