

#### 4. PRESSURE CONTROL EQUIPMENT

A 5000 PSI BOP System will be nipped up on the 8 5/8" casing and tested daily for operational. See attached 5000 PSI schematic.

#### 5. Cementing Program:

Surface Casing - Set with 300 sx Class C + 2% CaCl<sub>2</sub> (YLD 1.32 WT 14.8)

Intermediate Casing – Will lead with 850 sx Lite (YLD 2.48 WT 11.9). Tail in  
With 250 sx Class C (YLD 1.32 WT 14.8).

Production Casing - Set with 600 sx Super H Modified (YLD 1.67 WT 13.0)  
With the estimated top of cement being 9100'.