

## Part VII

- 1) Average daily rate - 16 bbl/hr  
Max daily rate - 20 bbl/hr  
400 - 480 bbls fluid to be injected per day
- 2) This is a closed system
- 3) Average injection pressure - 1800#  
Maximum injection pressure - 1900# - Determined by step -  
rate test
- 4) Injecting produced water
- 5) -

## Part VIII

See Order No. WXF548

## Part IX

1500 gallons 15% HCL with Corrosion Inhibitor,  
Iron sequesterant and clay stabilizer.

## Part XI

See Order No. WXF548

## Part XII

No faulting is shallow enough to affect aquifers  
existing in the area. There is no hydrologic  
connection between the injection zone and aquifers

RECEIVED  
FEB 26 1986  
O.C.D.  
HOBBS OFFICE