

DIAGRAMMATIC SKETCH OF DUAL COMPLETION INSTALLATION

Abu (Flowing) → Drinkard (Pumping) ←

11-3/4" OD Surface Casing Set at 336'
Cement Circulated

Cement Top @ 500'
(Continuous Fill from TD)

8-5/8" OD Intermediate Casing Set at 3314'

DRINKARD REEF (OIL)

Top: 7813'
Perforations: 7840-42'
7857-59'
7868-70'
7886-88'
7905-07'

Bottom: 8069'

Plug at 8757'

2-7/8" OD casing Set at 8790'

ABO REEF (OIL)

Top: 8318'

Perforations:

8512-14, 8531-33
8560-62, 8574-76
8587-89, 8598-8604
8633-35, 8654-56

Bottom: 8676'

Plug at 8760'

2-7/8" OD casing Set at 8793'

Drilled Total Depth 8800'

COMPANY: TEXACO Inc.
LEASE: State of New Mexico "R" NCT-4 Well No. 2
FIELD: Vacuum
DATE: March 5, 1962