

8 5/8" casing installation: 11"-5M BOP stack to be installed and tested by Yellow Jacket, Inc. to 3,000 psi before drilling the 8 5/8" casing shoe by Yellow Jacket, Inc. The BOP stack to consist of an annular BOP, blind ram BOP and one pipe ram BOP.

11. See Form 9-331C.
12. A. DST Program: (1) San Andres, (1) Middle Wolfcamp
B. Core: Possible in Wolfcamp
C. Mud Logging: Two Man Unit 2900'-TD
D. Wire Line Logs:

The following suite of logs will be run in both of the listed intervals:

GR/CNL/LDT/Cal	TD-2900' (GR/CNL to surf)
GR/Dual Laterolog-RXO	TD-2900'
GR-Sonic	TD-10,400'

13. No abnormal pressures anticipated with bottom hole pressures at TD expected to be 4500 psi. Bottom hole temperature 167^o F. No Hydrogen Sulfide expected in this know drilling area. No crooked hole or abnormal deviation problems.
14. Anticipated starting date to spud - on or before 11-9-86. Anticipated drilling time expected to be 36 (41 with DST & coring) days from surface to TD.

C. Nokes
10/9/86
0033c:100986