

7. AUXILIARY EQUIPMENT:

A geolograph will be in use from surface to total depth. Drill cuttings analysis equipment will be in use below the surface casing.

8. TESTING, LOGGING, AND CORING PROGRAMS:

Drill stem tests will be made if samples and other data indicate a test is warranted.

It is planned that electric logs will include GR-CNL-Density logs and GR-DLL logs.

No coring is planned.

9. ABNORMAL PRESSURES AND TEMPERATURES:

None anticipated.

10. It is planned that operations will commence upon approval of the application, with drilling and completion operations lasting about 30 days.