

7. Downhole Conditions:

Abnormally pressured zones: None.
Loss circulation zones: Anticipated in surface and intermediate portion of hole.
Maximum bottom hole temperature: 140° F.
Maximum bottom hole pressure: 6 #/gal gradient or less.

8. Anticipated Starting Date:

Plans are to drill this well as soon as possible after receiving approval. It should take approximately 20 days to drill with completion operations taking additional 10 days.