

**7. Downhole Conditions:**

Abnormally pressured zones:	None.
Loss circulation zones:	Anticipated in surface and intermediate portion of hole.
Maximum bottom hole temperature:	210° F.
Maximum bottom hole pressure:	6 #/gal gradient or less.

**8. Anticipated Starting Date:**

Plans are to drill this well as soon as possible after receiving approval. It should take approximately 40 days to drill with completion operations taking additional 10 days.