

7.

**Downhole Conditions:**

Abnormally pressured zones: None.  
Loss circulation zones: Anticipated in surface and intermediate portion of hole.  
Maximum bottom hole temperature: 140° F.  
Maximum bottom hole pressure: 6 #/gal gradient or less.

**8. Anticipated Starting Date:**

Plans are to drill this well as soon as possible after receiving approval. It should take approximately 20 days to drill with completion operations taking additional 10 days.