

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT

N.M. Oil Cons. Division  
1625 N. French Dr.  
Hobbs, NM 88240

NOT APPROVED  
Budget Bureau No. 1004-0135  
Expires: March 31, 1993  
5. Lease Designation and Serial No.  
NM 073240

**SUNDRY NOTICES AND REPORTS ON WELLS**

Do not use this form for proposals to drill or to deepen or reentry to a different reservoir.  
Use "APPLICATION FOR PERMIT—" for such proposals

**SUBMIT IN TRIPLICATE**

1. Type of Well

☐ Oil Well ☐ Gas Well ☒ Other WIW

2. Name of Operator

Robinson Oil, Inc.

3. Address and Telephone No.

P.O. Box 1829 Eunice, New Mexico 88231 505-394-3135

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

1650' FSL and 990' FEL Sec. 30, T19S, R33E

6. If Indian, Allottee or Tribe Name

7. If Unit or CA, Agreement Designation

8. Well Name and No.

Tonto #7

9. API Well No.

30-025-25897

10. Field and Pool, or Exploratory Area

Tonto-Yates Svn Rvrs, South

11. County or Parish, State

Lea New Mexico

12. CHECK APPROPRIATE BOX(s) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION

- ☐ Notice of Intent  
☒ Subsequent Report  
☐ Final Abandonment Notice


TYPE OF ACTION

- ☐ Abandonment  
☐ Recompletion  
☐ Plugging Back  
☐ Casing Repair  
☐ Altering Casing  
☐ Other WIW Re-enter P&A well
- ☐ Change of Plans  
☐ New Construction  
☐ Non-Routine Fracturing  
☐ Water Shut-Off  
☐ Conversion to Injection  
☐ Dispose Water

(Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)\*

Re-enter P & A'd well to make injection well. Drilled out plugs to a PBTD 3,113' Run in hole New 7" Baker Loc-set Pkr. (Plastic Coated), 17/8" Profile FL nipple w/overshot, Rice 2 3/8 to 2 7/8 Swedge Duoline 20 F.G., 2/38 tbg collar, 90 jts. 2 3/8 Rice Duoline 10 tbg. Ran with corrosion barrier rings. Set packer @ 2852.98 w/18 pts. tension. Circulate 110bbls fresh with 10 gals. conc. pkr. fluid. Returns cement H<sup>2</sup>O, stung pkr. back on, pressure to 500#, Held. Pump 2500 gals 15% with 2000# Rock salt, Isip 1300# 15 min 880#, Avg. PSI 2006# Avg. Rate 3.8 bpm 7" csg. to 2900' open hole to 3,113'



RECEIVED  
2001 SEP 11 AM 7:40

14. I hereby certify that the foregoing is true and correct

Signed Don E. Robinson

Title President

Date 09/10/01

(This space for Federal or State office use)

Approved by \_\_\_\_\_

Title \_\_\_\_\_

Date \_\_\_\_\_

Accepted For Record Only. By Accepting This Sundry Notice, No Approval Is Granted. The Application For Permit To Drill (APD) Expired September 9, 1998. Therefore, You May Not Have Had A Valid APD When You Reentered This Well. Need Responsibility Statement (Attached) To Change Operator.

make to any department or agency of the United States any false, fictitious or fraudulent statements  
on Reverse Side