

Page 2  
Well Prognosis  
#1 UT STATE

#### BLOWOUT PREVENTER SYSTEM

Drilling rig will be equipped with a 10" Shaffer Type E Series 900, blowout preventer with double rams and rated to 3,000# working pressure with Payne dual control 3,000# closing unit and Payne dual control 300# accumulator.

#### WELL SUPERVISION

Well site supervisions will be maintained from surface to total depth. Samples will be caught, washed and sacked from below surface string at 1,900' to total depth at 10-foot intervals. Mechanically recorded drilling time will be maintained from surface to total depth. Blowout preventer stack and casing head will be independently pressure tested before drilling into the Queen formation. A daily check of the blowout preventer system will be made from 4,600 to total depth.