


TYPE-RSRA BOP STACK

THREE PREVENTERS



COMPONENT SPECIFICATIONS

1. Screwed or flanged plug or gate valves -- 2" minimum nominal dia. -- same working pressure as "A" section.
2. Tee with tapped bullplug, needle valve, and pressure gauge.
3. Flanged plug or gate valve -- 2" minimum nominal dia. -- same working pressure as BOP stack. NOTE: Outer valves are optional if pump type trip tank is tied into Flowline Type.
4. Drilling spool of sufficient height to allow stripping with 2 flanged side outlets -- 3" choke and 2" kill line minimum nominal dia.
5. Flanged hydraulically controlled gate valve -- 3" minimum nominal dia. -- same working pressure as BOP stack.
6. Flanged plug or gate valve -- 3" minimum nominal dia. -- same working pressure as BOP stack.
7. Top of annular preventer must be equipped with an API flange ring gasket. All flange studs must be in place or holes filled in with screw type plugs.

NOTE:

- A. Unless specified otherwise in the Bid Letter and/or Contract, the contractor will furnish and maintain all components shown above Exxon's wellhead.
- B. The choke line between the drilling spool and choke manifold should not contain any bend or turn in the pipe body. Any bend or turn required should be made with a running tee with a blind flange or welded bullplug. All connections should be flanged or welded. All fabrications requiring welding must be done by a certified welder. Welds should be stress relieved when required.
- C. Plug valves should be equivalent to the Howco Lo-Torc and gate valves equivalent to the Cameron Type 'F'.

REC-6-25-90
173

RECEIVED

FEB 19 1990

OCB
HOBBS OFFICE