

No abnormal pressures or temperatures are foreseen. The anticipated bottom hole temperature at total depth is 100 degrees and maximum bottom hole pressure is 980 psig. Minimum hydrogen sulfide gas is possible and precautions will be taken in this area. No major loss circulation intervals have been encountered in adjacent wells.

8. Anticipated Starting Date and Duration of Operations:

The anticipated start date is August 1, 1996. The operation should require approximately 6 days. We plan to utilize only the existing well pad, therefore a Cultural Resources Examination is not necessary.