8. Well Testing: Drill stem testing will be preformed with the minimum number of personnel in the immediate area necessary to safely and adequately conduct the testing. The drill stem testing will be conducted during daylight hours and formation fluids will not be flowed to the surface. All drill stem testing operations conducted in an H2S environment will use the closed chamber method of testing.