

- (D) A mud logging unit complete with H₂S detector will be continuously monitoring drilling penetration rate and hydrocarbon shows from 5000; to TD.

8. Testing, Logging and Coring Program:

- (A) Drill stem tests will be run on the basis of drilling shows.
- (B) The electric logging program will consist of GR-Dual Laterolog-MSFL and GR-Sonic from TD to intermediate casing and GR-Compensated-Neutron-Density from TD to surface. Selected SVV cores will be taken in zones of interest.
- (C) No conventional coring is anticipated.
- (D) Further testing procedures will be determined after the 5-1/2" production casing has been cemented at TD based on drill shows, log evaluation and drill stem test results.

9. Abnormal Conditions, Pressures, Temperatures, & Potential Hazards:

No abnormal pressures or temperatures are anticipated. The estimated bottom hole temperature (BHT) at TD is 195° F and estimated maximum bottom hole pressure (BHP) is 5000 psig. No hydrogen sulfide or other hazardous gases or fluids have been encountered, reported or are known to exist at this depth in this area. No major loss circulation zones have been reported in offsetting wells.

10. Anticipated Starting Date and Duration of Operations:

Road and location work will not begin until approval has been received from the BLM. The anticipated spud date is March 1, 1997. Once commenced, the drilling operation should be finished in approximately 40 days. If the well is productive, an additional 30 days will be required for completion and testing before a decision is made to install permanent facilities.