

## PROPOSED CASING & CEMENTING PROGRAM

TOMAHAWK ST. 19 WELL NO. 1

2 nd Stage : Tail - 200 sx of 50:50 Poz Class "H" + 5% salt + 2% gel  
+ 3/10% retarder + 2/10% dispersant & antifoamer

Slurry Weight:	14.6 ppg
Slurry Yield:	1.27 cu.ft/sk
Water Requirement:	5.67 gal/sk