

8. Drillstem Testing, Logging, and Coring Programs:

- Drillstem tests will be run based on shows encountered while drilling.
- No logs are planned for the 11" hole section. The electric logging program for the 7-7/8" hole sections will consist of GR-Dual Laterolog MLL-BHC Sonic and GR Compensated Neutron--LithoDensity from TD to intermediate casing. Selected sidewell cores and RFT's may be taken in zones of interest.
- No conventional coring is anticipated.

9. Abnormal Conditions, Pressures, Temperatures, & Potential Hazards:

No abnormal pressures and/or temperatures are anticipated. No hydrogen sulfide or other hazardous gases or fluids are known to exist in this area. No major loss circulation zones are expected.

10. Anticipated Starting Date and Duration of Operations:

The anticipated start date will be December 12, 1999. Once commenced, drilling operations should be completed in approximately 35 days. If the well is productive, another 30 days will be required for completion work and facility installation.

