

PROPOSED CASING & CEMENTING PROGRAM

UNCAS "31" STATE WELL NO. 1

2 nd Stage : Lead - 300 sx of 35:65 Poz Class "H" + 5% salt + 6% gel
+ 3/10 % retarder + 2/10% antifoamer
Desired TOC = 8000'

Slurry Weight:	12.8 ppg
Slurry Yield:	1.95 cu.ft/sk
Water Requirement:	10.49 gal/sk

2 nd Stage : Tail - 150 sx of 50:50 Poz Class "H" + 5% salt + 2% gel
+ 3/10% retarder + 2/10% dispersant & antifoamer

Slurry Weight:	14.6 ppg
Slurry Yield:	1.27 cu.ft/sk
Water Requirement:	5.67 gal/sk