

UNITED STATES
DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEY

SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir. Use Form 9-331-C for such proposals.)

1. oil ☒ well gas ☐ well other ☐
2. NAME OF OPERATOR
Continental Oil Company
3. ADDRESS OF OPERATOR
Box 460, Hobbs, N.M. 88240.
4. LOCATION OF WELL (REPORT LOCATION CLEARLY. See space 17 below.)
AT SURFACE: *2310' FSL + 1980' FEL*
AT TOP PROD. INTERVAL: *Same*
AT TOTAL DEPTH: *Same*
16. CHECK APPROPRIATE BOX TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

REQUEST FOR APPROVAL TO:

- TEST WATER SHUT-OFF ☐
FRACTURE TREAT ☐
~~SHOOT OR~~ ACIDIZE ☒
REPAIR WELL ☐
PULL OR ALTER CASING ☐
MULTIPLE COMPLETE ☐
CHANGE ZONES ☐
ABANDON* ☐
(other) *Re-Perforate + Acidize*

SUBSEQUENT REPORT OF:

- ☐
☐
☐
☐
☐
☐
☐
☐
☐
☐

RECEIVED

APR 25 1978

U. S. GEOLOGICAL SURVEY
HOBBS, NEW MEXICO

5. LEASE
LC-03/622(a)
6. IF INDIAN, ALLOTTEE OR TRIBE NAME
7. UNIT AGREEMENT NAME
NMFU
8. FARM OR LEASE NAME
Sanderson A
9. WELL NO.
2
10. FIELD OR WILDCAT NAME
Eunice Monument Grayburg SA
11. SEC., T., R., M., OR BLK. AND SURVEY OR AREA
Sec. 11, T-20S, R-36E
12. COUNTY OR PARISH
Lea
13. STATE
N.M.
14. API NO.
15. ELEVATIONS (SHOW DF, KDB, AND WD)
3576' DF

17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*

IT IS Proposed TO INCREASE Production IN THE Subject Well as follows:

- 1. Load The Well with Tracked Fresh Wtr. + Pull Prod. Equip.*
- 2. Tag for fill and clean out to TD of necessary.*
- 3. Perf. additional pay at 3797'; 3813'; 18'; 22'; 42'; 50'; 60'; 67'; 90'; 92'; 95' w/2 JSPF.*
- 4. Acidize The above Perfs w/2000 Gals of 15% Acid.*
- 5. Scale Inhib. + with GYPTON T-44 (Champion).*
- 6. Pull Treating Equip + Re-run Prod. Equip + Return The well to Prod. Verbal Approval/Recd from Mr. Armando*

Subsurface Safety Valve: Manu. and Type _____ Set @ *4000' Ft*

18. I hereby certify that the foregoing is true and correct


SIGNED *Wm. R. Butterfield* TITLE *ADMIN. SUPV.* DATE *4-21-78*

(This space for Federal or State office use)

APPROVED BY _____
CONDITIONS OF APPROVAL, IF ANY:

TITLE _____

DATE _____



*See Instructions on Reverse Side

USGS (5), NMFU (4), F, 1e