

NO. OF COPIES RECEIVED	
DISTRIBUTION	
SANTA FE	
FILE	
U.S.G.S.	
LAND OFFICE	
OPERATOR	

NEW MEXICO OIL CONSERVATION COMMISSION

Form C-103
Supersedes Old
C-102 and C-103
Effective 1-1-85

5a. Indicate Type of Lease	
State ☐	Fee ☒
5. State Oil & Gas Lease No.	

SUNDRY NOTICES AND REPORTS ON WELLS (DO NOT USE THIS FORM FOR PROPOSALS TO DRILL OR TO LIFTEN OR PLUG BACK TO A DIFFERENT RESERVOIR. USE "APPLICATION FOR PERMIT -" (FORM C-101) FOR SUCH PROPOSALS.)		
1. ☐ OIL WELL ☒ GAS WELL ☐ OTHER		7. Unit Agreement Name
2. Name of Operator Graham Royalty, Ltd.		8. Farm or Lease Name Alaska-Cooper
3. Address of Operator 5429 LBJ Freeway, Suite 550 Dallas, TX 75240		9. Well No. 1
4. Location of Well UNIT LETTER <u>A</u> <u>660</u> FEET FROM THE <u>North</u> LINE AND <u>660</u> FEET FROM THE <u>East</u> LINE, SECTION <u>12</u> TOWNSHIP <u>20S</u> RANGE <u>36E</u> NMPM.		10. Field and Pool, or Wildcat Eunice Monument (G-SA)
11. Elevation (Show whether DF, RT, GR, etc.) 3,567' RT		12. County Lea

16. Check Appropriate Box To Indicate Nature of Notice, Report or Other Data
NOTICE OF INTENTION TO: SUBSEQUENT REPORT OF:

PERFORM REMEDIAL WORK ☐	PLUG AND ABANDON ☒	REMEDIAL WORK ☐	ALTERING CASING ☐
TEMPORARILY ABANDON ☐	CHANGE PLANS ☐	COMMENCE DRILLING OPNS. ☐	PLUG AND ABANDONMENT ☐
PULL OR ALTER CASING ☐	OTHER ☐	CASING TEST AND CEMENT JOBS ☐	OTHER ☐

17. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work) SEE RULE 1103.

Status: 13-3/8" CSA 248' w/200 sx cmt
9-5/8" CSA 2,296' w/500 sx cmt
7" CSA 3,763' w/75 sx cmt
PBSD - 3,710' TD - 3,890'
Open perfs 3,510' - 3,705' OA



THIS COMPLETION MUST BE NOTIFIED 24 HOURS BEFORE THE BEGINNING OF PLUGGING OPERATIONS FOR THIS CASE TO BE APPROVED

Procedure:

1. Set CIBP @ 3,450' x cap w/5 sx cmt.
2. Displace hole w/ 9.5 ppg mud-laden fluid.
3. Spot 25 sx cmt plug from 2,225' - 2,375'.
4. Spot 25 sx cmt plug from 175' - 325'.
5. Cut off csg. Weld on steel plate.
6. Install dry hole marker. Clean location.

7" WILL NEED TO BE PERFORATED @ 500' & CEMENTED W/100' PLUG INSIDE & OUT SIDE OF 7"

18. I hereby certify that the information above is true and complete to the best of my knowledge and belief.

SIGNED 	TITLE District Engineer	DATE 5/17/88
APPROVED BY 	TITLE DISTRICT 1 SUPERVISOR	DATE MAY 20 1988
CONDITIONS OF APPROVAL, IF ANY:		