

STATE OF NEW MEXICO
ENERGY AND MINERALS DEPARTMENT

OIL CONSERVATION DIVISION

P. O. BOX 2038
SANTA FE, NEW MEXICO 87501

Form C-103
Revised 10-1-79

NO. OF COPIES RECEIVED	
DISTRIBUTION	
SANTA FE	
FILE	
U.S.G.S.	
LAND OFFICE	
OPERATOR	

5a. Indicate Type of Lease	
State <input checked="" type="checkbox"/>	Fee <input type="checkbox"/>
5. State Oil & Gas Lease No.	
B 4096	

SUNDRY NOTICES AND REPORTS ON WELLS

(DO NOT USE THIS FORM FOR PROPOSALS TO DRILL OR TO DEEPEN OR PLUG BACK TO A DIFFERENT RESERVOIR. USE "APPLICATION FOR PERMIT" (FORM C-101) FOR SUCH PROPOSALS.)

1. OIL WELL <input checked="" type="checkbox"/> GAS WELL <input type="checkbox"/> OTHER <input type="checkbox"/>		7. Unit Agreement Name
2. Name of Operator		8. Farm or Lease Name
Amerada Hess Corporation		State "K"
3. Address of Operator		9. Well No.
Drawer D, Monument, New Mexico 88265		1
4. Location of Well		10. Field and Pool, or WHcut
UNIT LETTER F, 1980 FEET FROM THE North LINE AND 1980 FEET FROM		Monument - G/SA
THE West LINE, SECTION 29 TOWNSHIP 19-S RANGE 37-E NMPM.		
15. Elevation (Show whether DF, RT, GR, etc.)		12. County
3617 DF		Lea

Check Appropriate Box To Indicate Nature of Notice, Report or Other Data

NOTICE OF INTENTION TO:

SUBSEQUENT REPORT OF:

PERFORM REMEDIAL WORK <input checked="" type="checkbox"/>	PLUG AND ABANDON <input type="checkbox"/>	REMEDIAL WORK <input type="checkbox"/>	ALTERING CASING <input type="checkbox"/>
TEMPORARILY ABANDON <input type="checkbox"/>	CHANGE PLANS <input type="checkbox"/>	COMMENCE DRILLING OPNS. <input type="checkbox"/>	PLUG AND ABANDONMENT <input type="checkbox"/>
PULL OR ALTER CASING <input type="checkbox"/>	OTHER <input type="checkbox"/>	CASING TEST AND CEMENT JOBS <input type="checkbox"/>	

17. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work) SEE RULE 1103.

Plan to pull rods, pump, tubing and install BOP. Run cement bond log. Run bridge plug, pkr. and set bridge plug at depth determined by bond log. Load tbq. and test plug at 2500#. Cap plug with 10' of sand. Perf. 7" csg. w/2 shots as determined by bond log. TIH w/cement retainer & set accordingly. Circ. cement to surface. WOC drill out cement and retainer. Test squeeze job to 800#. If OK, recover bridge plug, re-run tbq., pump and rods and resume production.

18. I hereby certify that the information above is true and complete to the best of my knowledge and belief.

SIGNED E.B. Fisher TITLE Supv. Adm. Ser. DATE May 9, 1980

APPROVED BY John Runyan TITLE DATE MAY 15 1980

CONDITIONS OF APPROVAL, IF ANY: