

7. MIRU PULLING UNIT AND REVERSE UNIT. INSTALL BOP AND KILL WELL W/ 10 BBLS OF 2% KCL WTR MIXED W/ SURFACTANT.

8. TIH W/ 2 3/8" OD J-55 TEXAS PATTERN ON 2 3/8" OD EUE 4.70 #/FT J-55 8 RD PRODUCTION TBG. MIRU AIR DRILLING EQUIPMENT AND CLEAN OUT FILL. PUH AND HANG TBG OPEN ENDED @ +/- 3134'. RDMO AIR DRILLING EQUIPMENT AND REVERSE UNIT.

9. REMOVE BOP, INSTALL TBG WRAP AROUND AND LAND TBG IN WELL HEAD. NIPPLE UP WELLHEAD. SWAB WELL IN. RDMO PULLING UNIT. MONITOR GAS PRODUCTION TO SALES.