


SALIENT OIL COMPANY
 State "F" Lease
 Sec. 17, T-20-S R-37-E
 Lea County, New Mex.



- Oil well
- ★ Gas well
- ★ Dual Completion
- ✕ Plugged & Abandoned
- Blue lines lease lines
- Red lines dedicated Acreage

OCC
Hobbs

DC-345
due 9/28/56
NSP-322
due 10/17/56

Box 38, Hobbs, New Mexico

September 11, 1956

New Mexico Oil Conservation Commission
P. O. Box 671
Santa Fe, New Mexico

Early! what formation
in Monument Pool
is oil coming
from WWM

Re: IN THE MATTER OF APPLICATION OF SKELLY OIL
COMPANY FOR AN ADMINISTRATIVE ORDER GRANT-
ING PERMISSION TO DUAL COMPLETE ITS STATE "W"
NO. 2 IN THE EUNONT GAS POOL AND THE MONUMENT
OIL POOL AND FOR AN ORDER FOR A 160 ACRE NON-
STANDARD GAS PRODUCTION UNIT.

Gentlemen:

Comes now SKELLY OIL COMPANY, a Delaware Corporation with offices in Tulsa, Oklahoma, and Hobbs, New Mexico, hereby petitioning the Secretary of the New Mexico Oil Conservation Commission for administrative approval for an order granting permission to dual complete its State "W" Well No. 2 as a gas well in the Eunont Gas Pool and an oil well in the Monument Oil Pool and also for an order for a 160 acre non-standard gas production unit in the Eunont Gas Pool, Lea County, New Mexico, and in support thereof does state:

1. That the petitioner is the operator of a gas lease confined by the SW/4 Section 17, Township 20 South, Range 37 East N.M.P.M., Lea County, New Mexico, and concerns but a single royalty owner.
2. That the petitioner's State "W" No. 2 is located 660' from the south line and 1980' from the east line of the section and was completed March 1957, as a Monument oil well.
3. That the petitioner will dually complete its State "W" No. 2 in a manner described below.
 - a. Perforate the Poreose 3348' to 3450' for Eunont Gas.
 - b. Run 2 1/2" tubing with a Baker Model "D" Retainer Production Packer to be set at around 3660' so as to segregate the two producing intervals.
 - c. Produce the Monument oil from open hole 3678' to 3720' through 2" tubing and the Eunont gas through the tubing-casing annulus.