

TIDEWATER OIL COMPANY
 SKETCH OF PRESENT COMPLETION & PROPOSED DUAL COMPLETION
 S. J. SARKEYS NO. 1
 Unit B, Sec. 26, T-21-S, R-37-E
 Lea County, New Mexico

PRESENT

PROPOSED

3-3/8" 36# set
 293'. Cemented
 w/300 sacks

8-5/8" 32# H-40 @
 2807'. Cemented
 w/1400 sacks

2-3/8" tbg. 4.7# H-40
 @ 6553'. Pinned collar
 & perforated nipple on
 bottom

5 1/2" 17# J-55 set @
 6560'. Cemented
 w/500 sacks

PBTD 6555'

Old Drinkard Perfs:
 6460'-6554'.

2 - Strings 2-1/16"
 tbg. Long string set
 @ 6430'. Short string
 set at 5720'.

Parallel tubing
 anchor at 5720'

Blinebry perfs. @
 approx. 5730-5840'.

Baker Model D packer
 @ 6370'

New Drinkard perfs.
 @ approx. 6400'-6435'.

Bridge plug set @
 approx. 6450' w/2 sks.
 cement dumped on top.

Note: No temperature survey available. Calculated fill up behind 5 1/2" casing,
 3200' from well head. Cement volumes on 13-3/8" & 8-5/8" calculated to
 circulate.