

South Eunice Unit #14
Pg 2

- w/20 bbls maximum 2% KCL TFW if necessary. Reverse out excess cement & P.O.H. Wait on cement 24 hrs.
- ⑨ Prepare to test squeeze. G.I.H w/ bit & 2 7/8" workstring. Drill out float collar & float shoe & P.O.H. Pressure test squeeze to 1000 psi for 15 mins. If test fails, resqueeze. Clean out to 3830. G.I.H w/ seal nipple & Land 5' seal bore section at bottom of lined.
- ⑩ Acidize 7 Rins Queen flood interval at 4-6 BPM w/ max surface pressure of 2000 psi w/ 120 bbls 15% HCL- FE acid w/ 84 gals Checker-Sol inhibited for 24 hrs at 100° F plus 600 lbs graded rock salt mixed in 5 bbls gelled 9# brine. Flush w/ 100 bbls 9# brine. Swab well. P.O.H.
- ⑪ G.I.H w/ anchor seal assembly & 2 3/8" plastic coated injection tbg. Load backside w/ 12 gals Conoco No. 1 pkr fluid plus 6 gals Conoco #2 pkr fluid mixed in 120 bbls 2% KCL TFW. Latch tbg into 7" pkr.
- ⑫ Return well to injection.
- ⑬ If you have any questions, please contact Jay Vashler at 393-4141.

RECEIVED

JAN 28 1988

COPIES
HOBBS OFFICE