WELL NAME SEMU EUMONT NO. 118		FIELD NMFU	
ATTACHMENT	NO.	REQUIRED	NOT REQUIRED
CASING CENTRALIZERS, SCRATCHERS		X	
CEMENTING		X	
MUD PROGRAM		X	
WELL PLAN OUTLINE		X	
PORE PRESSURE - FRAC GRADIENT			
PROJECTED PROGRESS			
CROSS SECTION OR WELL COURSE			
HYDRAULICS PROGRAM			
BIT PROGRAM			
VENDER USAGE LIST			

PROPOSED WELL PLAN

•

DRILLING AND COMPLETION PROCEDURE

- 0'--1300'- Drill a 12-1/4" hole. Run and cement casing. (See cement and casing programs) WOC 18 hours, pressure test casing to 600 psi and drill out.
- 2. 1300'-3770' Drill a 7-7/8" hole. Drill out shoe and test formation to 200 psi. Run and cement casing. (See cement and casing programs)
- 3. Detailed completion procedure to be prepared after open hole logs are analyzed.

NOTE: Casing pressure tests should be 30 minutes in duration.