#### Submit to Appropriate

#### State of New Mexico

Form C-101

District Office
State Lease-6 copies

Energy, Minerals and Natural Resources Department

Revised 1-1-89

Fee Lease-5 copies	OIL CONSERVATION DIVISION										
P.O. Box 2088											
DISTRICT   P.O. Box 1980, Hobbs, N	IM 88240	Santa	a Fe, I	New Mexic	o 875	04-2088 API NO. (assigned by	v OCD on New W	elie)			
DISTRICT II		30	-025	-31723							
P.O. Drawer Dd, Artesia, DISTRICT III	NM 88210	5. Indicate Type of Lesse STATE FEE X									
1000 Rio Brazos Rd., Azt	ec, Nm 87410					6. State Oil & Gas Lesse No.					
APPLICATION FOR PERMIT TO DRILL, DEEPEN, OF PLUG BACK							ana ina ara	4.35.24.244.24.24.24.27.32.34.			
1a. Type of Work:	1. Type of Work: 7. Lease					7. Lesse Name or L ARROWHEAD	-				
b. Type of Well:	<del></del>		_								
METT X	GAS OTHER WELL	SINGLE ZONE	<u> </u>	MULTIPLE ZONE							
2. Name of Operator						8. Well No.					
	RON U.S.A. INC.	8001104				188					
3. Address of Operator	( 1150 MIDLAND T	ROOM 310		D MAATTU	34/0	9. Pool name or Wi					
4. Well Location	( 1150, MIDLAND, T	X /9/02 AI	IN: P.	R. WATTHE	-WS	ARROWHEAD	GRAYBUR	G			
Unit Letter	D : 730	Feet From The	NOR	TH	Line an	520	Feet From The	WEST_Line			
Section	12	Township	22\$		Range	36E	NMPM	LEA County			
		1	O. Propo			11. Formation		12. Rotary or C.T.			
Michigan Commenter	and the State of t			4500		GRAYBURG		ROTARY			
13. Elevation (Show DF,		14. Kind & Status Plug Bond 15. Dr			16. Dri	lg Contractor	16. Date Work v	vill start			
3495		<u> </u>	BLANK			D-RIC		9-10-92			
17	PROPOSEI	CASING AND	CEME	NT PROGRA	M						
SIZE OF HOLE	SIZE OF CASING	WEIGHT PER FOO	т	SETTING DEPT	Н	SACKS OF CEMENT		EST. TOP			
12 1/4"	8 5/8"	23		1350'		800		SURFACE			
7 7/8"	5 1/2"	15.5		4500'		900		SURFACE			
				-							
MUD PROGRAM: 0-1350' FRESH WATER SPUD MUD, 9.0 PPG. 1350'-4500' BRINE WATER AND STARCH SYSTEM, 10.0 PPG.  BOPE EQUIPMENT: 2000 PSI WORKING PRESSURE, SEE ATTACHED CHEVRON U.S.A. CLASS II DRAWING.  IN ABOVE SPACE DESCRIBE PROPOSED. IF PROPOSAL IS TO DEEPEN OR PLUG BACK, GIVE DATA ON PRESENT PRODUTIVE ZONE AND PROPOSED.											
	. GIVE BLOWOUT PREVENTER					<del></del>					
I hereby certify that the information above is true and complete to the best of my knowledge and belief.  SIGNATURE						<u> </u>	DATE	9-4-92			
TYPE OR PRINT NAME	P.R. MATTH	IEWS					TELEPHONE NO.	(915)687-7812			
ORIGI	NAL SIGNED BY JERF	Y SEXTON						CED 000			
APPROVED BY BISTRICT I SUPERVISORITLE DATE											

RECEIVED SEP 0 8 1992

OCO HOBBS OFFICE

State Lease - 4 copies
Fee Lease - 3 copies

## State of New Mexico Energy, Minerals and Natural Resources Department

Form C-102 Revised 1-1-89

### OIL CONSERVATION DIVISION

DISTRICT I P.O. Box 1980, Hobbs, NM 88240

P.O. Box 2088
Santa Fe, New Mexico 87504-2088

DISTRICT II P.O. Drawer DD, Artesia, NM 88210

### WELL LOCATION AND ACREAGE DEDICATION PLAT


DISTRICT III 1000 Rio Brazos Rd., Aztec, NM 87410

All Distances must be from the outer boundaries of the section

Operator	CHEVRON U.S	S.A. INC.	Lease ARROW	HEAD GRAYBURG	TINL	Well No. 188							
Unit Letter	Section	Township	Range		County								
D	12	22 SOUTH	3	6 EAST NIMPIN		LEA							
Actual Footage Location of Well:  730 feet from the NORTH line and 520 feet from the WEST line													
730 fee Ground Level Elev			520   Pool	feet from	the WES	Dedicated Acreage:							
3495.2'	GRAYBL		ARROWHEAD	/GB		40 Acres							
		the subject well by colored	pencil or hachure	marks on the plat belo	<b>7.</b>								
2. If more than one lease is dedicated to the well, outline each and identify the ownership thereof (both as to working interest and royalty).													
3. If more than one lease of different ownership is dedicated to the well, have the interest of all owners been consolidated by communitization, unitization, force-pooling, etc.?													
Yes No If answer is "yes" type of consolidation													
If answer is "no" list of owners and tract descriptions which have actually been consolidated. (Use reverse side of this form necessary.													
No allowable w	vill be assigned to					nitization, forced-pooling,							
otherwise) or until a non-standard unit, eliminating such interest, has been approved by the Division.													
Y////	- N		i		OPERAT	OR CERTIFICATION							
			ļ	İ		eby certify the the information vin is true and complete to the							
	CHEVRON USA INC		1	1	l	enviedge and beitef.							
520'	H.T. MATTERN NCT-E		ļ		-								
	<b>N</b>		!		Signature	Wathern							
	<b>−157</b> ′		!	,	Printed Nar								
7	S		!		P.R. M	atthews							
177777	77775		+-		Position	AL ACCIOTANT							
	1		!		TECHNIC	يدب ومدود ومطاطعات الطاطلات والأساء							
	1		ļ i		CHEVRO	N U.S.A. INC.							
	i		t i		Date								
<b>.</b>	i		! !		9-	4-92							
	į		1		SURVEY	OR CERTIFICATION							
					I hereby certi	fy that the well location shown							
	ļ	1	1		1	was plotted from field notes of							
1	!		1		supervisor,	· · · · · · · · · · · · · · · · · · ·							
	!		I		correct to i	the best of my knowledge and							
	ļ		l	1	bolief.								
1	ļ		l		Date Surve	· 1							
	i		Į.	·	Signature	GUST 28, 1992							
		- <del></del>	+-		Profession	Chiles By Co							
			!			IN MEY							
j	! !		!			HEW MEXICO							
	l I		Į.		14	( root) thele							
1	J I		!		DE 116								
	[ ]		ļ										
`	1 1		!		Certificate	POFESSONNE POSON, 3239							
						7555 THY L JONES. 7977							
0 330 660	990 1320 1650	1980 2310 2640 2	000 1500	000 500 0	a - v	92-11-1233							

# CHEVRON DRILLING REFERENCE SERIES VOLUME ELEVEN WELL CONTROL AND BLOWOUT PREVENTION

### D. CLASS II-B BLOWOUT PREVENTER STACK:




The Class II-B preventer stack is designed for drilling or workover operations. It is composed of a single hydraulically operated annular preventer on top, then a drilling spool, and a single blind ram preventer on bottom. In an alternate configuration, a single pipe ram preventer may be substituted for the annular preventer. The choke and kill lines are installed onto the drilling spool and must have a minimum internal diameter of 2". An emergency kill line may be installed on the wellhead. As the maximum anticipated surface pressure of this stack is less than 2000 psi, screwed connections may be used. All components must be of steel construction. The Class II-B blowout preventer stack is shown to the left in Figure 11J.3.

# CHEVRONDRILLING REFERENCE SERIES VOLUME ELEVEN WELL CONTROL AND BLOWOUT PREVENTION

#### C. CLASS II CHOKE MANIFOLD

The Class II choke manifold is suitable for all Class Ii workovers and drilling operations. The Class II choke manifold is shown below in Figure 11J.7. Specific design features of the Class II choke manifold include:

- 1. The manifold is attached to the tubing/casing head when a Class II-A preventer stack is use. This hook-up is only recommended for Class II workover operations.
- 2. The manifold is attached to a drilling spool or top ram preventer side outlets when a Class II-B preventer stack is in use.
- 3. The minimum internal diameter is 2" (nominal) for outlets, flanges, valves and lines.
- 4. Includes two steel gate valves in the choke line at the wellhead/drilling spool outlet. The inside choke line valve may be remotely controlled (HCR).
- 5. Includes one manually adjustable choke which is installed on the side of the manifold cross. Steel isolation gate valves are installed between the choke and the cross, and downstream of the choke.
- 6. Includes one bleed line installed on the side of the manifold cross which is isolated by a steel gate valve.
- 7. Includes a pressure gauge suitable for drilling service which can display the casing pressure within view of the choke operator.
- 8. Screwed connections may be used in lieu of flanges or clamps.



RECEIVED

P 0 to 1992

Rev. 1/1/89