

7. The anticipated testing, logging, and coring procedures to be used, including drill stem testing procedures, equipment, and safety measures.

- a. DST Program: None
- b. Core: None
- c. Mud Logging: Two-man unit 4600' to TD.
- d. Logs to be run: CNL-FDC/GR/CAL: TD-ICP CNL/CR to surface  
DIL/SFL/GR:TD-ICP

8. The expected bottom-hole pressure and any anticipated abnormal pressures, temperatures or potential hazards that are expected to be encountered, such as lost circulation zones and hydrogen sulfide. The operator's plans for mitigating such hazards shall be discussed. Should the potential to encounter hydrogen sulfide exist, the mitigation procedures shall comply with the provisions of Onshore Oil and Gas Order No. 6.

No abnormal pressures are anticipated. Bottom hole pressures at TD expected to be 4300 psi. Bottom hole temperature 140° F. Attached is a H<sub>2</sub>S contingency plan.

9. Any other facets of the proposed operation which the operator wishes for BLM to consider in reviewing the application.

Anticipated start date is November 1993. Anticipated drilling time expected to be 21 days from surface to TD.

RECEIVED

JOE HOBBS  
OFFICE