

6. EVALUATION PROGRAM:

Samples: 10' samples from surface casing to T.D.
Logging: SD-DSNL from T.D. to surface casing with GR-DSNL
from T.D. to surface. DLL-Micro SFL Guard from
T.D. to surface casing.
Coring: As warranted.
DST'S: As warranted.

7. DOWNHOLE CONDITIONS:

Abnormally pressured zones: NONE
Loss Circulation Zones: Anticipated in surface hole only.
Maximum Bottom Hole Temperature: <100 degrees F.
Maximum Bottom Hole Pressure: 5#/gal. gradient or less.

8. ANTICIPATED STARTING DATE:

Plans are to spud this well approximately the first week
of October 1995. It should take approximately 6 days to
drill the well with completion operations taking an
additional 10 days.